


DETAIL A



**FOOTING
DETAIL**

NOTE: ALL METAL SURFACES SHALL BE COATED WITH TWO COATS OF HEAVY COAL TAR PAINT.




**STANDARDS &
SPECIFICATIONS**

REVISED:

**AIR RELEASE
AND VACUUM
RELIEF VALVE**

DATE:

DRAWING NO. 200-01



ELEVATION

SHEET 1 OF 2




STANDARDS &
SPECIFICATIONS

REVISED:

**BUTTERFLY
VALVE**


DATE:

DRAWING NO. 200-02



DETAIL A

- 1 1/4" I P THREADED OUTLET
- 1 1/4" I P THREADED CORP STOP MUELLER H-15025
- 1 1/4" COPPER TUBING
- 1 1/4" I P THREADED CORP STOP MUELLER H-15025
- 1 1/4" THREADED GATE VALVE (TYP. ONE EACH SIDE OF VALVE)
- 1 1/4" MUELLER CORP STOP H-15002 AND FIELD TAP (DUCTILE IRON PIPE ONLY)



DETAIL B

SHEET 2 OF 2



STANDARDS &
SPECIFICATIONS

REVISED:


**BUTTERFLY
VALVE**

DATE:

DRAWING NO. 200-03

FOR VALVES INSTALLED OUTSIDE OF PAVEMENT. CONSTRUCT 18" SQ. x 6" THICK CONCRETE COLLAR AND SET 2" ABOVE GRADE.

FOR VALVES INSTALLED IN PAVEMENT SET VALVE BOX TO GRADE REQUIRED BY CITY/COUNTY OR STATE AGENCY.



NOTES:

NOT TO SCALE

1. THIS DETAIL IS FOR BUTTERFLY VALVE INSTALLATIONS 20-INCHES IN DIAMETER OR SMALLER.
2. CARE SHALL BE TAKEN WHEN INSTALLING VALVES TO ASSURE PROPER SUPPORT OF THE VALVE. THE AUTHORITY MAY REQUIRE 3/4" CRUSHED ROCK TO BE INSTALLED UNDER THE VALVE TO PROVIDE PROPER SUPPORT.
3. VALVES SHALL NOT BE PLACED IN CONCRETE CROSS PANS.
4. OPERATING NUTS SHALL NOT BE SET CLOSER THAN THREE (3) FEET TO FINAL GRADE OR DEEPER THAN FIVE (5) FEET FROM FINAL GRADE. OPERATOR EXTENSIONS SHALL BE CONNECTED TO VALVE OPERATOR USING SET SCREW.
5. BUTTERFLY VALVE AND OPERATOR SHALL BE POLYETHYLENE WRAPPED.




STANDARDS &
SPECIFICATIONS

REVISED:


**BUTTERFLY
VALVE
DIRECT BURY**

DATE:

DRAWING NO. 200-04



PLAN



ELEVATION

SHEET 1 OF 3



STANDARDS &
SPECIFICATIONS

REVISED:

**BLOW-OFF VALVE
12 " AND SMALLER
PIPE**

DATE:

DRAWING NO. 200-05

TOP SECTION OF VALVE BOX,
TYLER 6860 SERIES OR EQUAL
(EXTENSIONS IF REQUIRED).
HOLE TO BE DRILLED IN
FIELD OR CAST-IN-PLACE

VALVE BOX SUPPORT
PLATE, 12" X 12" X 3/16".
ANCHOR WITH 2 1/2" SS
EXPANSION ANCHORS

24" STD RING AND COVER

60" DIA. PRECAST
CONCRETE FLAT MH
COVER (ASTM C478)

2 - 4 BRICK
COURSES OR
CONCRETE RINGS

OPERATOR EXTENSION

STD. STEPS

EXTENSION GUIDE

60" DIA. PRECAST
CONCRETE MANHOLE
SECTIONS (ASTM C478)

VARIABLE

MAIN SIZE X 6" TEE
ROTATED 45°
DOWNWARD

6" GATE
VALVE

6" X 90° FLANGED
ELBOW UP

MASTIC
SEALANT

6" - 45° BEND

ADJUSTABLE
SUPPORT

7' SQ. CONCRETE
PAD TO REST ON
UNDISTURBED SOIL

MIN 6 x 6 - 10 x 10 WWF

ELEVATION

NOTES:

1. FIRE HYDRANT MAY BE USED AS AN
ALTERNATE BLOW-OFF. SEE DETAIL.
2. ALL METAL SURFACES SHALL BE
COATED WITH TWO COATS OF
HEAVY COAL TAR PAINT.

SHEET 2 OF 3




STANDARDS &
SPECIFICATIONS

REVISED:

**BLOW-OFF VALVE
16" + LARGER
MAINS**

DATE:

DRAWING NO. 200-06



SHEET 3 OF 3





STANDARDS &
SPECIFICATIONS

REVISED:

**BLOW-OFF VALVE
FIRE HYDRANT
ALTERNATE**

DATE:

DRAWING NO. 200-07



CARRIER PIPE NOMINAL DIA.	CASING PIPE		MINIMUM RUNNER SIZE
	MIN. O.D.	MIN. WALL THICK	
4"	12"	0.188"	2" x 4"
6"	16"	0.250"	2" x 4"
8"	18"	0.282"	2" x 4"
12"	22"	0.344"	2" x 4"
16"	28"	0.406"	2" x 6"
20"	32"	0.469"	2" x 6"

- NOTES:
- 1.) NEOPRENE OR PVC RUNNERS MAY BE USED AS AN ALTERNATIVE TO TREATED REDWOOD.
 - 2.) TRENCH LAID CASINGS SHALL BE DESIGNED AND INSTALLED TO CONDUIT STANDARDS.



STANDARDS &
SPECIFICATIONS

REVISED:

**BORE CASING
DETAIL**

DATE:

DRAWING NO. 200-08




TABLE OF DIMENSIONS FOR CLAMPS																									
PIPE DIAMETER	BAR SIZE	A		B		C		D		E		F		G		H		I		J	K	BOLT SIZE		PIPE DIAMETER	
		BELL CLAMP	BODY CLAMP	BELL CLAMP	BODY CLAMP	BELL CLAMP	BODY CLAMP	BELL CLAMP	BODY CLAMP	BELL CLAMP	BODY CLAMP	BELL CLAMP	BODY CLAMP	BELL CLAMP	BODY CLAMP	BELL CLAMP	BODY CLAMP	BELL CLAMP	BODY CLAMP	BELL CLAMP	BODY CLAMP	BELL CLAMP	BODY CLAMP		
4	1-1/2 x 1/2	9	7-3/8	3	4	1-1/2	1-1/2	6-1/4	4-3/4	2-5/8	1-7/8			3/8	3/8	1-1/4	1-1/4	2-1/4	2-1/2	5/8	2-1/2	3 x 1-1/2	2-1/2 x 3/8	4	
6	2 x 1/2	11-1/4	9-5/8	3	4	1-1/2	1-1/2	8-1/2	6-7/8	3-3/4	2-15/16							2-1/4	2-1/2	1/2	3-3/4	3-1/2 x 1/2	3-1/2 x 1/2	6	
8	2-1/2 x 1/2	13-5/8	11-7/8	3-1/2	4	1-1/2	1-1/2	10-3/4	9-1/8	4-7/8	4-1/6							2-1/4	2-1/2	5/8	4-3/4	4-1/2 x 1/2	4 x 1/2	8	
12	2-1/2 x 5/8	18-1/4	16-3/8	3-1/2	4	1-1/2	1-1/2	15-1/8	13-1/4	7-1/16	6-1/8							2-1/4	2-1/2	13/16	6-3/4	4-1/2 x 5/8	4-1/2 x 5/8	12	
16	3 x 3/4	23-1/8	20-5/8	4	4-1/2	1-1/2	1-1/2	19-3/4	17-3/8	9-1/4	8-1/16	1-1/4	1-1/4	1/4	1/4	1-1/2	1-1/2	2-1/4	2-3/4	15/16	8-15/16	5-1/2 x 5/8	5-1/2 x 5/8	16	
20	3 x 3/4	27-1/2	25	4	4-1/2	1-1/2	1-1/2	24-1/8	21-5/8	11-5/16	10-1/16	1-1/2	1-1/2	3/8	3/8	1-3/4	1-3/4	2-1/4	2-1/2	1	11-1/16	5-1/2 x 5/8	5-1/2 x 5/8	20	
24	RODS AND CLAMPS NOT ALLOWED.																							24	

NOTE: ALL DIMENSIONS IN INCHES.

NOTE: NOT FOR USE WITH 18" & 20" D.I. COMPACT FITTINGS.




STANDARDS &
SPECIFICATIONS

REVISED:

CLAMP
DETAIL

DATE:

DRAWING NO. 200-09



3000 P.S.I.
CONCRETE
VIBRATED
IN PLACE

PIPE SIZE	NO. OF LONGITUDINAL BARS AND LOCATION	
6"	4 – NO. 4 BARS	1 EACH CORNER
8"	4 – NO. 4 BARS	1 EACH CORNER
10"	8 – NO. 4 BARS	3 EACH SIDE
12"	8 – NO. 4 BARS	3 EACH SIDE
15"	8 – NO. 4 BARS	3 EACH SIDE
18"	8 – NO. 4 BARS	3 EACH SIDE
21"	12 – NO. 4 BARS	4 EACH SIDE
24"	12 – NO. 4 BARS	4 EACH SIDE
27"	12 – NO. 4 BARS	4 EACH SIDE
30"	12 – NO. 4 BARS	4 EACH SIDE
33"	12 – NO. 4 BARS	4 EACH SIDE
36"	16 – NO. 4 BARS	5 EACH SIDE





STANDARDS &
SPECIFICATIONS

REVISED:

**CONCRETE
ENCASEMENT**

DATE:

DRAWING NO. 200-10




STANDARDS &
SPECIFICATIONS

REVISED:

WASTE METERING AND SAMPLING

DATE:

DRAWING NO. 200-11



GENERAL NOTES:

1. FOR INSTALLATION IN ROADWAYS, DRIVEWAYS, SIDEWALKS, OR PARKING AREAS PRIOR APPROVAL REQUIRED.
2. NO CONCRETE FLOOR ALLOWED IN METER PIT.
3. METER PIT SHALL BE CONSTRUCTED OF ANY COMBINATION OF CONCRETE RINGS TOTAL - 48" IN LENGTH.
4. ADJUSTMENT RINGS SHALL BE 2", 3", 4" OR 6" IN HEIGHT AND SHALL BE INSERTED BETWEEN THE DOME AND TOP RING.
5. NO CONNECTIONS OR CHANGES IN PIPE DIAMETER SHALL BE MADE FROM THE MAIN TAP TO A DISTANCE OF FIVE FEET BEYOND THE METER PIT WALL ON THE OUTLET SIDE.
6. LID SHALL SAY "WATER METER"

METER SIZE	A	B	C	D
5/8"x 3/4"	12-5/8"	7-13/16"	7-13/16"	4"
3/4"	14-1/4"	9-5/16"	8-15/16"	5"
1"	17-1/4"	11-1/16"	11-1/4"	6"

SHEET 1 OF 2



STANDARDS &
SPECIFICATIONS

REVISED:

**OUTSIDE SETTING
1" METERS
AND BELOW**

DATE:

DRAWING NO. 200-12

LIST OF MATERIALS

1. RING AND COVER – J'MARK NO. J-2290 (81 LBS.) OR APPROVED EQUAL WITH INTERNAL FROST LID.
2. METER PIT – ARCO NO. 24-4 PRECAST MANHOLE (24" DIA.) OR APPROVED EQUAL.
3. SERVICE LINE – COPPER TUBING TYPE K, SAME DIAMETER AS THE METER.
4. METER YOKE ASSEMBLY – FORD 80 SERIES COPPER SETTER OR APPROVED EQUAL.
5. SHUT-OFF VALVE.
6. CORPORATION STOP. A SADDLE MAY BE REQUIRED.

ADDITIONAL NOTES

1. THE AUTHORITY SHALL INSPECT FROM THE MAIN TO THE BUILDING PRIOR TO BACKFILLING.
2. IF THE SURFACE IS NOT TO FINAL GRADE AT THE TIME OF THE METER INSTALLATION, THE PROPERTY OWNER SHALL RAISE OR LOWER THE METER PIT ACCESS MANHOLE TO MATCH THE FINAL GRADE.
3. THE METER SHALL BE A POSITIVE DISPLACEMENT ROCKWELL OR NEPTUNE TRIDENT 8, READING IN GALLONS.
4. CAP TYPE TOP LID SHALL BE CAST IRON ONLY. THE INNER LID SHALL BE CAST IRON, ALUMINUM OR RUBBER. THE ALUMINUM SHALL BE COATED WITH A POLYMER SUCH AS EPOXY. CAST IRON SHALL BE COATED WITH AN ASPHALT BASE PAINT.

SHEET 2 OF 2




STANDARDS &
SPECIFICATIONS

REVISED:

**OUTSIDE SETTING
1' METERS
AND BELOW**

DATE:

DRAWING NO. 200-13



SHEET 1 OF 2



STANDARDS &
SPECIFICATIONS

REVISED:

**DOMESTIC METER PIT
PRESSURE REDUCING
1-1/2" AND UP**

DATE:

DRAWING NO. 200-14

LIST OF MATERIALS

1. CORPORATION STOP VALVE.
2. CURB STOP VALVE AND BOX W/ 2" OPERATOR NUT AND FLARED COPPER ENDS.
CURB STOP VALVE BOX MUST BE A 3-PIECE BOX WITH 5-1/4" BARREL AND WIDE OVAL BASE (TYLER 6860 SERIES, OR APPROVED EQUAL).
3. SERVICE LINE – COPPER TUBING TYPE K, SAME DIAMETER AS THE METER.
4. METER – POSITIVE DISPLACEMENT ROCKWELL OR NEPTUNE TRIDENT 8, READING IN GALLONS
5. RING AND COVER – J'MARK NO. J1163 (125 LBS. COVER) OR APPROVED WITH WATER CAST INTO COVER.
6. METER PIT – 48" DIA. PRECAST MANHOLE ASTM C478, FLAT TOP.
7. BALL VALVE– FORD BALL VALVE CURB STOP W/ FEMALE THREAD IRON PIPE & FLARED COPPER ENDS OR EQUAL. (2 REQ.)
8. BRASS FLANGE COUPLING
9. FORD LOK-PAK ADJUSTMENT COUPLING W/2 STAINLESS STEEL SET SCREWS.
10. STOP & WASTE VALVE W/FLARED COPPER ENDS.

NOTES

1. THE DISTRICT SHALL INSPECT FROM THE MAIN TO THE BUILDING PRIOR TO BACKFILLING.
2. IF THE SURFACE IS NOT TO FINAL GRADE AT TIME OF THE METER INSTALLATION, THE PROPERTY OWNER SHALL RAISE OR LOWER THE METER PIT ACCESS MANHOLE TO MATCH THE FINAL GRADE.
3. COUPLINGS SHALL BE PROVIDED ON UPSTREAM AND DOWNSTREAM SIDES OF METER TO ALLOW FOR REMOVAL.
4. TOP STEP 18" – 24" BELOW THE SURFACE, REMAINDER SPACED AT 12" INTERVALS.

SHEET 2 OF 2



STANDARDS &
SPECIFICATIONS

REVISED:

**DOMESTIC METER PIT
PRESSURE REDUCING
1-1/2" AND UP**

DATE:


DRAWING NO. 200-15

NOTE:

1 — PLACEMENT OF STOP BOX CAN VARY FROM A MAXIMUM OF 5 FEET OUTSIDE THE PROPERTY LINE TO THE PROPERTY LINE. PLACEMENT OF THE STOP BOX OUTSIDE THE PROPERTY LINE IS PREFERRED.

2 — OWNER'S RESPONSIBILITY FOR LEAK REPAIR SHALL BE UP TO AND INCLUDING THE TUBE NUT WHICH THREADS ONTO THE CURB STOP. OWNER'S RESPONSIBILITY FOR REPAIRS OTHER THAN LEAK REPAIR EXTENDS TO THE CORPORATION STOP.

3 — ACWWA WILL REPAIR LEAKS ON SERVICE LINES WHEN NOTIFIED, FROM THE CORPORATION STOP TO CURB STOP.




STANDARDS &
SPECIFICATIONS

REVISED:


DOMESTIC SERVICE OUTSIDE METER INSTALLATION

DATE:


DRAWING NO. 200-16



FIRELINE OR DOMESTIC CONNECTION WITH MAIN EXTENSION



FIRELINE OR DOMESTIC CONNECTION



FIRELINE CONNECTION WITH DOMESTIC SERVICE TEE

NOTE: 4" FIRELINE CONNECTION WITH 1-1/2" OR 2" DOMESTIC TEE SHALL BE PLUGGED AND TAPPED WITH AWWA CC THREADS FOR APPLICABLE SIZE.

- | | | | |
|---|--|----|--|
| 1 | EXISTING MAIN | 8 | CONCRETE KICKBLOCK |
| 2 | TAPPING SLEEVE | 9 | M.J. ANCHORING TEE (SWIVEL TEE WHERE APPLICABLE) |
| 3 | TAPPING VALVE | 10 | M.J. VALVE |
| 4 | DOUBLE SPIGOT PIPE | 11 | DOMESTIC SERVICE TEE OR SERVICE TAP |
| 5 | PROPERTY LINE VALVE | 12 | POLYETHYLENE WRAPPED |
| 6 | TIE RODS (MEGALUGS ARE NOT ACCEPTABLE) | 13 | 90° FITTING (BEND FOR 2" & SMALLER) |
| 7 | PIPE CLAMP | 14 | VALVE OR CURBSTOP AS NOTED ON PLANS & CONTINUE PER APPLICABLE METER DETAIL |



**STANDARDS &
SPECIFICATIONS**

REVISED:


**2" AND LARGER
FIRELINE
CONNECTION**

DATE:

DRAWING NO. 200-17

NOTE:
PIPE MUST BE "FULLY" RESTRAINED
WITH EITHER RODDING OR
MECHANICAL JOINT RESTRAINT
SUCH AS MEGALUGS, OR APPROVED
EQUAL.

HYDRANT SHALL BE
PLUMB IN ALL
DIRECTIONS WITH
PUMPER NOZZLE
FACING STREET AND
SHALL BE PAINTED
YELLOW



MUELLER A-473 OR WATEROUS WB-67 OR M&H HYDRANT




STANDARDS &
SPECIFICATIONS

REVISED:

FIRE HYDRANT DETAIL

DATE:

DRAWING NO. 200-18



GENERAL NOTES:

1. FOR INSTALLATION IN ROADWAYS, DRIVEWAYS, SIDEWALKS, OR PARKING AREAS PRIOR APPROVAL REQUIRED.
2. NO CONCRETE FLOOR ALLOWED IN METER PIT.
3. METER PIT SHALL BE CONSTRUCTED OF ANY COMBINATION OF CONCRETE RINGS TOTAL - 48" IN LENGTH.
4. ADJUSTMENT RINGS SHALL BE 2", 3", 4" OR 6" IN HEIGHT AND SHALL BE INSERTED BETWEEN THE DOME AND TOP RING.
5. NO CONNECTIONS OR CHANGES IN PIPE DIAMETER SHALL BE MADE FROM THE MAIN TAP TO A DISTANCE OF FIVE FEET BEYOND THE METER PIT WALL ON THE OUTLET SIDE.
6. LID SHALL SAY "WATER METER".

METER SIZE	A	B	C	D
5/8"x 3/4"	12-5/8"	7-13/16"	7-13/16"	4"
3/4"	14-1/4"	9-5/16"	8-15/16"	5"
1"	17-1/4"	11-1/16"	11-1/4"	6"

SHEET 1 OF 2



STANDARDS &
SPECIFICATIONS

REVISED:

IRRIGATION
1" METERS
AND BELOW

DATE:

DRAWING NO. 200-19

LIST OF MATERIALS

1. RING AND COVER – J'MARK NO. J-2290 (81 LBS.) OR APPROVED EQUAL WITH INTERNAL POST
2. METER PIT – ARCO NO. 24-4 PRECAST MANHOLE (24" DIA.) OR APPROVED EQUAL.
3. SERVICE LINE – COPPER TUBING TYPE K, SAME DIAMETER AS THE METER.
4. METER YOKE ASSEMBLY – FORD 80 SERIES COPPER SETTER OR APPROVED EQUAL.
5. SHUT-OFF VALVE.
6. CORPORATION STOP. A SADDLE MAY BE REQUIRED.
7. RE-USE SOURCE WATERLINE.

NOTES

1. THE AUTHORITY SHALL INSPECT FROM THE MAIN TO THE BUILDING PRIOR TO BACKFILLING.
2. IF THE SURFACE IS NOT TO FINAL GRADE AT TIME OF THE METER INSTALLATION, THE PROPERTY OWNER SHALL RAISE OR LOWER THE METER PIT ACCESS MANHOLE TO MATCH THE FINAL GRADE.
3. THE METER SHALL BE A POSITIVE DISPLACEMENT ROCKWELL OR NEPTUNE TRIDENT 8, READING IN GALLONS.
4. COUPLINGS SHALL BE PROVIDED ON UPSTREAM AND DOWNSTREAM SIDES OF METER TO ALLOW FOR REMOVAL.
5. TRACER WIRE TO BE ATTACHED TO ALL WATER LINES.
6. CAP TYPE TOP LID SHALL BE CAST IRON ONLY. THE INNER LID SHALL BE CAST IRON, ALUMINUM OR RUBBER. THE ALUMINUM SHALL BE COATED WITH A POLYMER SUCH AS EPOXY. CAST IRON SHALL BE COATED WITH AN ASPHALT BASE PAINT.
7. FOR INSTALLATION IN ROADWAYS, DRIVEWAYS, SIDEWALKS, OR PARKING AREAS PRIOR APPROVAL REQUIRED.
8. NO CONCRETE FLOOR ALLOWED IN METER PIT.
9. METER PIT SHALL BE CONSTRUCTED OF ANY COMBINATION OF CONCRETE RINGS TOTAL – 48" IN LENGTH.
10. ADJUSTMENT RINGS SHALL BE 2", 3", 4" OR 6" IN HEIGHT AND SHALL BE INSERTED BETWEEN THE DOME AND THE TOP RING.
11. NO CONNECTIONS OR CHANGES IN PIPE DIAMETER SHALL BE MADE FROM THE MAIN TAP TO A DISTANCE OF FIVE FEET BEYOND THE METER PIT WALL ON THE OUTLET SIDE.

SHEET 2 OF 2




STANDARDS &
SPECIFICATIONS

REVISED:

**IRRIGATION
1" METERS
AND BELOW**

DATE:


DRAWING NO. 200-20



SECTIONAL PLAN

NO SCALE

METER SIZE	A	B	C	D
5/8"x 3/4"	12-5/8"	7-13/16"	7-13/16"	4"
3/4"	14-1/4"	9-5/16"	8-15/16"	5"
1"	17-1/4"	11-1/16"	11-1/4"	6"



SECTION A

NO SCALE

TO RPBP DEVICE
AND IRRIGATION

(SEE DETAIL A,
SHEET 9 OF 9)

SHEET 3 OF 9



STANDARDS &
SPECIFICATIONS

REVISED:

**IRRIGATION METER
BACKFLOW PREVENTER
3/4" THRU 1"**

DATE:

DRAWING NO. 200-21

LIST OF MATERIALS

1. RING AND COVER – J'MARK NO. J-2290 (81 LBS.) OR APPROVED EQUAL WITH INTERNAL POST
2. METER PIT – ARCO NO. 24-4 PRECAST MANHOLE (24" DIA.) OR APPROVED EQUAL.
3. SERVICE LINE – COPPER TUBING TYPE K, SAME DIAMETER AS THE METER.
4. METER YOKE ASSEMBLY – FORD 80 SERIES COPPER SETTER OR APPROVED EQUAL.
5. SHUT-OFF VALVE.
6. CORPORATION STOP. A SADDLE MAY BE REQUIRED.
7. EXISTING DOMESTIC SOURCE WATERLINE.
8. FUTURE RE-USE SOURCE WATERLINE.
9. CURB STOP WITH 2" VALVE NUT ADAPTER AND BOX.

NOTES

1. THE AUTHORITY SHALL INSPECT FROM THE MAIN TO THE BUILDING PRIOR TO BACKFILLING.
2. IF THE SURFACE IS NOT TO FINAL GRADE AT TIME OF THE METER INSTALLATION, THE PROPERTY OWNER SHALL RAISE OR LOWER THE METER PIT ACCESS MANHOLE TO MATCH THE FINAL GRADE.
3. THE METER SHALL BE A POSITIVE DISPLACEMENT ROCKWELL OR NEPTUNE TRIDENT 8, READING IN GALLONS.
4. COUPLINGS SHALL BE PROVIDED ON UPSTREAM AND DOWNSTREAM SIDES OF METER TO ALLOW FOR REMOVAL.
5. CONTRACTOR TO PROVIDE CONNECTION FROM CURBSTOP TO PLUG AND ALL APPERTENCES FOR RE-USE LINE.
6. TRACER WIRE TO BE ATTACHED TO ALL WATER LINES.
7. CAP TYPE TOP LID SHALL BE CAST IRON ONLY. THE INNER LID SHALL BE CAST IRON, ALUMINUM OR RUBBER. THE ALUMINUM SHALL BE COATED WITH A POLYMER SUCH AS EPOXY. CAST IRON SHALL BE COATED WITH AN ASPHALT BASE PAINT.
8. FOR INSTALLATION IN ROADWAYS, DRIVEWAYS, SIDEWALKS, OR PARKING AREAS PRIOR APPROVAL REQUIRED.
9. NO CONCRETE FLOOR ALLOWED IN METER PIT.
10. METER PIT SHALL BE CONSTRUCTED OF ANY COMBINATION OF CONCRETE RINGS TOTAL – 48" IN LENGTH.
11. ADJUSTMENT RINGS SHALL BE 2", 3", 4" OR 6" IN HEIGHT AND SHALL BE INSERTED BETWEEN THE DOME AND THE TOP RING.
12. NO CONNECTIONS OR CHANGES IN PIPE DIAMETER SHALL BE MADE FROM THE MAIN TAP TO A DISTANCE OF FIVE FEET BEYOND THE METER PIT WALL ON THE OUTLET SIDE.

SHEET 4 OF 9





**STANDARDS &
SPECIFICATIONS**

REVISED:

**IRRIGATION METER
BACKFLOW PREVENTER
3/4" THRU 1"**

DATE:

DRAWING NO. 200-22



LIST OF MATERIALS

1. CORPORATION STOP VALVE.
2. CURB STOP VALVE AND BOX W/ 2" OPERATOR NUT AND FLARED COPPER ENDS.
CURB STOP VALVE BOX MUST BE A 3-PIECE BOX WITH 5-1/4" BARREL AND WIDE OVAL BASE (TYLER 6860 SERIES, OR APPROVED EQUAL).
3. SERVICE LINE – COPPER TUBING TYPE K, SAME DIAMETER AS THE METER.
4. METER – POSITIVE DISPLACEMENT ROCKWELL OR NEPTUNE TRIDENT 8, READING IN GALLONS
5. RING AND COVER – J'MARK NO. J1163 (125 LBS. COVER) OR APPROVED WITH WATER CAST INTO COVER.
6. METER PIT – 48" DIA. PRECAST MANHOLE ASTM C478, FLAT TOP.
7. BALL VALVE– FORD BALL VALVE CURB STOP W/ FEMALE THREAD IRON PIPE & FLARED COPPER ENDS OR EQUAL. (2 REQ.)
8. BRASS FLANGE COUPLING
9. FORD LOK-PAK ADJUSTMENT COUPLING W/2 STAINLESS STEEL SET SCREWS.
10. STOP & WASTE VALVE W/FLARED COPPER ENDS.

NOTES

1. THE DISTRICT SHALL INSPECT FROM THE MAIN TO THE BUILDING PRIOR TO BACKFILLING.
2. IF THE SURFACE IS NOT TO FINAL GRADE AT TIME OF THE METER INSTALLATION, THE PROPERTY OWNER SHALL RAISE OR LOWER THE METER PIT ACCESS MANHOLE TO MATCH THE FINAL GRADE.
3. COUPLINGS SHALL BE PROVIDED ON UPSTREAM AND DOWNSTREAM SIDES OF METER TO ALLOW FOR REMOVAL.
4. TOP STEP 18" – 24" BELOW THE SURFACE, REMAINDER SPACED AT 12" INTERVALS.
5. REFER TO IRRIGATION SYSTEM RP-TYPE BACKFLOW PREVENTER SCHEMATIC DETAIL IF METER TO BE USED FOR RE-USE, IRRIGATION OR EFFLUENT WATER PURPOSES.

SHEET 6 OF 9




**STANDARDS &
SPECIFICATIONS**

REVISED:

**IRRIGATION METERS
1-1/2" THRU 2"
WITHOUT PRV**

DATE:

DRAWING NO. 200-24



SHEET 7 OF 9



STANDARDS & SPECIFICATIONS

REVISÉD:

IRRIGATION METERS
1-1/2" THRU 2"
WITH PRV

DATE:

DRAWING NO. 200-25

LIST OF MATERIALS

1. CORPORATION STOP VALVE.
2. CURB STOP VALVE AND BOX W/ 2" OPERATOR NUT AND FLARED COPPER ENDS.
CURB STOP VALVE BOX MUST BE A 3-PIECE BOX WITH 5-1/4" BARREL AND WIDE OVAL
BASE (TYLER 6860 SERIES, OR APPROVED EQUAL)
3. SERVICE LINE – COPPER TUBING TYPE K, SAME DIAMETER AS THE METER.
4. METER – POSITIVE DISPLACEMENT ROCKWELL OR NEPTUNE TRIDENT 8, READING IN
GALLONS
5. RING AND COVER – J'MARK NO. J1163 (125 LBS. COVER) OR APPROVED
WITH WATER CAST INTO COVER.
6. METER PIT – 48" DIA. PRECAST MANHOLE ASTM C478, FLAT TOP.
7. BALL VALVE– FORD BALL VALVE CURB STOP W/ FEMALE THREAD IRON PIPE
& FLARED COPPER ENDS OR EQUAL. (2 REQ.)
8. BRASS FLANGE COUPLING.
9. FORD LOK-PAK ADJUSTMENT COUPLING W/2 STAINLESS STEEL SET SCREWS.
10. STOP & WASTE VALVE W/FLARED COPPER ENDS.

NOTES

1. THE DISTRICT SHALL INSPECT FROM THE MAIN TO THE BUILDING PRIOR TO
BACKFILLING.
2. IF THE SURFACE IS NOT TO FINAL GRADE AT TIME OF THE METER INSTALLATION,
THE PROPERTY OWNER SHALL RAISE OR LOWER THE METER PIT ACCESS MANHOLE TO
MATCH THE FINAL GRADE.
3. BRASS FLANGE COUPLINGS SHALL BE PROVIDED ON UPSTREAM AND DOWNSTREAM SIDES
OF METER TO ALLOW FOR REMOVAL.
4. TOP STEP TO BE 18" TO 24" BELOW THE SURFACE, AT 12" VERTICAL INTERVALS.
5. REFER TO IRRIGATION SYSTEM RP-TYPE BACKFLOW PREVENTER SCHEMATIC DETAIL IF
APPLICABLE.

SHEET 8 OF 9




STANDARDS &
SPECIFICATIONS

REVISED:


**IRRIGATION METERS
1-1/2" THRU 2"
WITH PRV**

DATE:

DRAWING NO. 200-26



PLAN



DETAIL A

NO SCALE

SHEET 9 of 9



STANDARDS &
SPECIFICATIONS

REVISED:

IRRIGATION SYSTEM
WITH RPBP

DATE:


DRAWING NO. 200-27

NOTE:

1 — PLACEMENT OF STOP BOX CAN VARY FROM A MAXIMUM OF 5 FEET OUTSIDE THE PROPERTY LINE TO THE PROPERTY LINE. PLACEMENT OF THE STOP BOX OUTSIDE THE PROPERTY LINE IS PREFERRED.

2 — OWNER'S RESPONSIBILITY FOR LEAK REPAIR SHALL BE UP TO AND INCLUDING THE TUBE NUT WHICH THREADS ONTO THE STOP AND WASTE VALVE. OWNER'S RESPONSIBILITY FOR REPAIRS OTHER THAN LEAK REPAIR EXTENDS TO THE CORPORATION STOP.

3 — ACWWA WILL REPAIR LEAKS ON SERVICE LINES WHEN NOTIFIED, FROM THE CORPORATION STOP TO STOP AND WASTE VALVE.




**STANDARDS &
SPECIFICATIONS**

REVISED:



**DOMESTIC METER
AND IRRIGATION
WITH RPBP**

DATE:

DRAWING NO. 200-28



PLAN



DETAIL

DIMENSIONS

ALLOWABLE PIPE DIAMETER INCHES	BOLT SIZE	NO . OF BOLTS REQUIRED
4	3/4"	2
6	3/4"	2
8	3/4"	2
10	3/4"	4
12	3/4"	6

NOTES:

- 1 - THE BOLT SHALL BE MANUFACTURED OF "COR-TEN" OR APPROVED EQUAL.
- 2 - THE BOLT MAY BE HEAT TREATED.




STANDARDS &
SPECIFICATIONS

REVISED:


**JOINT RESTRAINT
DETAIL**

DATE:

DRAWING NO. 200-29




11¼°, 22½°, 45° AND 90° BENDS




TEE

NOTES:

- 1.) BEARING SURFACES SHOWN IN CHART ARE MINIMUM.
- 2.) BASED ON 150 PSI INTERNAL PIPE PRESSURE PLUS WATER HAMMER.
4",6",8" AND 12" WATER HAMMER = 110 P.S.I.
16",20" AND 24" WATER HAMMER = 70 P.S.I.
- 3.) CONCRETE MUST BE MINIMUM OF 3000 PSI, AND CURE FOR 24 HOURS BEFORE TAMPING OR COMPACTING.
- 4.) BASED ON 3,000 psf SOIL BEARING CAPACITY.
- 5.) NA = NOT APPLICABLE.



DEAD END



TYPICAL CROSS SECTION

MINIMUM BEARING SURFACE AREA

(IN SQUARE FEET)

SIZE OF PIPE	BENDS				TEE OR DEAD END
	11¼°	22½°	45°	90°	
4"	1.00	1.00	1.00	N.A.	1.50
6"	1.00	1.25	2.25	4.25	3.00
8"	1.00	2.00	4.00	8.00	5.25
12"	2.25	4.50	8.75	12.00	11.25
16"	3.75	7.50	14.50	27.00	19.00
20"	5.00	10.00	19.50	35.50	25.00
24"	7.00	14.00	27.75	51.00	36.00




STANDARDS &
SPECIFICATIONS

REVISED:


CONCRETE
KICKBLOCKS

DATE:


DRAWING NO. 200-30



MECHANICAL JOINT RESTRAINT



WEDGE DETAIL



BOLT HOLE DETAIL

DIMENSIONS

	NOMINAL PIPE SIZE	NO. OF BOLTS	NO. OF WEDGES	K2 INCHES	J INCHES	F INCHES	M INCHES	
P V C	4"	2	2					P V C
	6"	6	3	11.12	9.50	7.00	0.88	
	8"	6	4	13.37	11.75	9.15	1.00	
	10"	8	6	15.62	14.00	11.20	1.00	
	12"	8	8	17.88	16.25	13.30	1.25	
D I	4"	4	2					D I
	6"	6	3	11.12	9.50	7.00	0.88	
	8"	6	4	13.37	11.75	9.15	1.00	
	10"	8	6	15.62	14.00	11.20	1.00	
	12"	8	8	17.88	16.25	13.30	1.25	






STANDARDS &
SPECIFICATIONS

REVISED:

**MECHANICAL JOINT
RESTRAINT**

DATE:

DRAWING NO. 200-31



FIELD INSTALLATION—POLYETHYLENE WRAP

- STEP-1 PLACE TUBE OF POLYETHYLENE MATERIAL AROUND PIPE PRIOR TO LOWERING PIPE INTO TRENCH.
- STEP-2 PULL THE TUBE OVER THE LENGTH OF THE PIPE. TAPE TUBE TO PIPE AT JOINT. FOLD MATERIAL AROUND THE ADJACENT SPIGOT END AND WRAP WITH THREE CIRCUMFERENTIAL TURNS OF TWO-INCH WIDE PLASTIC TAPE TO HOLD PLASTIC TUBE AROUND SPIGOT END.
- STEP-3 ADJACENT TUBE OVERLAPS FIRST TUBE AND IS SECURED WITH PLASTIC ADHESIVE TAPE. THE POLYETHYLENE TUBE MATERIAL COVERING THE PIPE WILL BE LOOSE. EXCESS MATERIAL SHALL BE NEATLY DRAWN UP AROUND THE PIPE BARREL, FOLDED INTO AN OVERLAP ON TOP OF THE PIPE AND HELD IN PLACE BY MEANS OF PIECES OF THE PLASTIC TAPE AT APPROXIMATELY THREE TO FIVE FOOT INTERVALS.



STANDARDS &
SPECIFICATIONS

REVISED:

**POLYETHYLENE
WRAP**

DATE:

DRAWING NO. 200-32



STANDARDS & SPECIFICATIONS

REVISED:

RESTRAINED PIPE

DATE:


DRAWING NO. 200-33


ROD DIAMETER, GRADE & LENGTH OF RESTRAINED PIPE

PIPE SIZE	4"			6"			8"			12"			16"			20"			24"		
FITTING	D	L	G	D	L	G	D	L	G	D	L	G	D	L	G	D	L	G	D	L	G
90° BEND TEE, PLUG	3/4"	30'	M.S.	3/4"	45'	M.S.	3/4"	60'	M.S.	3/4"	86'	H.S.	1"	108'	H.S.	1 1/4"	132'	H.S.	—	155'	—
VALVE	3/4"	30'	M.S.	3/4"	45'	M.S.	3/4"	60'	M.S.	3/4"	86'	H.S.	1"	108'	H.S.	1 1/4"	132'	H.S.	—	155'	—
45° BEND	3/4"	9'	M.S.	3/4"	13'	M.S.	3/4"	18'	M.S.	3/4"	25'	M.S.	1"	32'	M.S.	3/4"	39'	H.S.	—	45'	—
22 1/2° BEND	3/4"	1'	M.S.	3/4"	4'	M.S.	3/4"	5'	M.S.	3/4"	7'	M.S.	3/4"	8'	M.S.	3/4"	10'	M.S.	—	12'	—
11 1/4° BEND	3/4"	1'	M.S.	3/4"	1'	M.S.	3/4"	1'	M.S.	3/4"	2'	M.S.	3/4"	2'	M.S.	3/4"	3'	M.S.	—	3'	—

NOTES:

- 1.) LENGTH OF RESTRAINED PIPE MEASURED EACH WAY FROM VALVES AND BENDS.
- 2.) CLAMPS, RODS & MEGALUGS NOT ALLOWED FOR 24" & LARGER PIPES.
- 3.) D=DIAMETER, L=LENGTH, G=GRADE
M.S.=MILD STEEL, H.S.=HIGH STRENGTH.
- 4.) MINIMUM 4.5' GROUND COVER REQUIRED.
- 5.) BASED ON 150 PSI INTERNAL PRESSURE
- 6.) M.S. = MILD STEEL ROD ASTM A36.
- 7.) H.S. = HIGH STRENGTH ROD ASTM A193 GRADE B7.
- 8.) NUTS SHALL BE ASTM A307 GRADE A OR B HEXAGON HEAVY SERIES.
HIGH STRENGTH NUTS SHALL BE ASTM A 194, GRADE 2H.
- 9.) SEE TIE ROD DETAIL DRAWING. ALSO, TIE ROD COUPLING DETAILS,
CLAMP DETAILS AND SET CLAMP DETAILS.
- 10.) LENGTH REFERS TO THE AMOUNT OF PIPE WHICH MUST BE RESTRAINED
TOGETHER AND IS NOT NECESSARILY THE LENGTH OF THE RODS.
- 11.) LENGTH OF RESTRAINED PIPE CHART IS ALSO FOR THE LENGTH OF JOINT
RESTRAINT FOR EBBA IRON MEGALUGS OR UNIFLANGE PIPE RESTRAINT DEVICES.
- 12.) CROSSES MUST BE RESTRAINED IN ALL APPLICABLE DIRECTIONS.
- 13.) 12" AND SMALLER IN LINE VALVES AND TEES SHALL HAVE A MECHANICAL JOINT RESTRAINT DEVICE
ON EACH SIDE OF THE FITTING OR VALVE. MECHANICAL JOINT RESTRAINT DEVICE SHALL BE: DIP -
EBAA 1100 SERIES, UNI-FLANGE SERIES 1400, OR EQUIVALENT; PVC - EBAA MEGALUG 2000 PV SERIES,
UNI-FLANGE SERIES 1500, OR EQUIVALENT.
- 14.) A SECOND VALVE WILL BE REQUIRED TO BE CLOSED WHEN EXCAVATING NEXT TO AN EXISTING VALVE.





- NOTES:
1. PAVING SHALL COMPLY WITH LOCAL AUTHORITY JURISDICTION.
 2. TRENCH WALLS TO BE SUPPORTED AS REQUIRED BY O.S.H.A.
 3. MINIMUM COVER TO BE BELOW OFFICIAL STREET GRADE.
 4. MINIMUM TRENCH WIDTH = PIPE O.D. + 12"
MAXIMUM TRENCH WIDTH = PIPE O.D. + 24"




STANDARDS &
SPECIFICATIONS

REVISED:


TYPICAL TRENCH SECTION

DATE:

DRAWING NO. 200-34



TIE ROD DETAILS



WASHER DETAIL

TIE RODS			
A	B	C	
ROD DIAMETER	THREAD LENGTH	ROD LENGTH	GRADE
3/4", 1"	6"	1' TO 11' & 20'	MS
3/4", 1-1/2"	ALL THREAD	1' TO 11' & 20'	HS

WASHERS		
D	E	G
WIDTH	HOLE DIAMETER	THICKNESS
5"	1/8" Larger than Rod Ø	1/2"
6"	1/8" Larger than Rod Ø	5/8"

NOTE:

- 1.) SEE TIED JOINTS, ROD DIMENSIONS SHEET.
- 2.) SEE CLAMP DETAILS AND DIMENSIONS FOR PROPER PLACEMENT OF WASHERS.
- 3.) MS=MILD STEEL
HS=HIGH STRENGTH






**STANDARDS &
SPECIFICATIONS**

REVISED:


**TIE ROD AND
WASHER DETAIL**

DATE:

DRAWING NO. 200-35



DETAIL 'A'



DETAIL 'B'




STANDARDS &
SPECIFICATIONS

REVISED:

TRACE WIRE
DETAILS

DATE:

DRAWING NO. 200-36



UTILITY CROSSING
N.T.S.

- 1.) LENGTH OF EXTENSION OF PIPE AND HARNESS RODS SHALL BE IN ACCORDANCE WITH THESE ENGINEERING STANDARDS.
- 2.) ALL WATER MAINS TWELVE (12") INCHES OR SMALLER, WHICH CROSS UNDER DISTRICT CONDUITS SHALL BE DUCTILE IRON.
- 3.) A BORED CROSSING MAY BE REQUIRED BY THE ENGINEER.




STANDARDS &
SPECIFICATIONS

REVISED:

UTILITY
CROSSING

DATE:

DRAWING NO. 200-37



NOTES:

1. GATE VALVES SHALL OPEN CCW AND BE RESILIENT SEAT MEETING REQUIREMENTS OF AWWA C509.
2. FITTINGS SHALL BE WRAPPED WITH 8 MIL MINIMUM THICKNESS POLYETHYLENE SHEETING.
3. VALVE BOX TOP SHALL BE SET 1/2" BELOW FINAL ASPHALT PAVEMENT GRADE.
4. PROVIDE MARKER POST WHERE NECESSARY.




STANDARDS &
SPECIFICATIONS



REVISED:

VALVE BOX DETAIL

DATE:

DRAWING NO. 200-38






STANDARDS &
SPECIFICATIONS

REVISED:

INSIDE DROP
MANHOLE

DATE:



DRAWING NO. 300-01




ELEVATION

NOTE:

1. STEPS SHALL BE LOCATED ABOVE THE EXIT PIPE IN A STRAIGHT LINE, 12" ON CENTER (O.C.) VERTICALLY.
2. 60" DIA. MANHOLES SHALL HAVE A 30" STANDARD RING AND COVER, J-MARK NO. J-1361 OR APPROVED EQUAL.
3. 48" DIA. MANHOLES SHALL HAVE A 24" STANDARD RING AND COVER, J-MARK NO. J-1161 OR APPROVED EQUAL.
4. MORTAR SHALL COVER THE LEVELING COURSES AND RING TO WITHIN 1" FROM THE SURFACE, AND SHALL BE USED ON THE INSIDE OF THE BARREL AT THE JOINTS.
5. ALL MANHOLES IN EXCESS OF 20' IN DEPTH SHALL HAVE AN INTERMEDIATE GRATING LOCATED AT THE CENTER OF THE DEPTH.
6. THE WORD "SEWER" SHALL BE BOLDLY CAST ON ALL COVERS.



ALTERNATE FLAT LID



FLEXIBLE PLASTIC
JOINT MATERIAL
(K.T. SNYDER
"RAM-NEK" OR
APPROVED EQUAL)

DETAIL A




STANDARDS &
SPECIFICATIONS

REVISED:


**STANDARD
MANHOLE**

DATE:


DRAWING NO. 300-02




PLAN OF BASE



SECTION A



SECTION B



BASE DETAIL

REINFORCE BASE WITH #4'S AT 12" E.W., OR WWF 6X6-W10 x W10 ALL 3" CLEAR FROM BOTTOM.

NOTE:

1. STRAIGHT SECTIONS MAY BE LAID THROUGH THE MANHOLE WITH CROWN REMOVED.
2. SECTIONS NOT LAID THROUGH THE MANHOLE SHALL DROP A MINIMUM OF 0.2'.
3. BENCHES SHALL SLOPE 2 IN/FT.
4. THERE SHALL BE A JOINT MADE AT THE EDGE OF THE MANHOLE BASE.
5. THE TOP OF THE BASE SHALL BE LEVEL IN ALL CASES.
6. SHORT STUBS SHALL BE INSTALLED ON VCP AND RCP LINES WHERE THE LINE ENTERS AND LEAVES THE BASE.




STANDARDS &
SPECIFICATIONS

REVISED:

STANDARD
MANHOLE

DATE:

DRAWING NO. 300-03




STANDARDS &
SPECIFICATIONS

REVISED:

MANHOLE MARKER POST

DATE:

DRAWING NO. 300-04



- NOTES:
1. PAVING SHALL COMPLY WITH LOCAL AUTHORITY JURISDICTION.
 2. TRENCH WALLS TO BE SUPPORTED AS REQUIRED BY O.S.H.A.
 3. MINIMUM COVER TO BE BELOW OFFICIAL STREET GRADE.
 4. MINIMUM TRENCH WIDTH = PIPE O.D. + 12"
MAXIMUM TRENCH WIDTH = PIPE O.D. + 24"




STANDARDS &
SPECIFICATIONS

REVISED:

**SEWER
TRENCH**

DATE:

DRAWING NO. 300-05



TYPICAL MANHOLE SECTION
WITH ECCENTRIC CONE

NOTES:

1. ALL JOINTS TO BE RUBBERNEK OR RAMNEK IF ABOVE THE WATER TABLE, FLEXIBLE PLASTIC SEALING COMPOUND IF BELOW THE WATER TABLE, AS PER SPECIFICATION.
2. ALL JOINTS SHALL BE DOUBLE SEALED WITH FLEXIBLE PLASTIC JOINT SEALING MATERIAL TO EXTRUDE INTO MANHOLE, AND BE TRIMMED OFF.
3. ALL MANHOLES PLACED IN THE "OPEN SPACE" AREAS SHALL BE INSTALLED WITH THE RING AND COVER AT AN ELEVATION THAT IS 6" ABOVE FINAL GRADE WITH A COLLAR OF CONCRETE. A MARKER POST SHALL BE INSTALLED NEAR BY. SEE MARKER POST DETAIL.
4. STEPS INSTALLED OVER DOWNSTREAM INVERT OF MANHOLE.
5. 60" OR LARGER DIAMETER MANHOLES REQUIRE A 30" OPENING.
6. SEE EITHER CAST-IN-PLACE OR PRECAST MANHOLE BASE DETAIL
7. ALL COVERS TO BE CASTINGS, INC. J-1161 FOR 24" OPENING OR J-1361 FOR 30" OPENINGS.
8. RING AND COVER SHALL BE CASTINGS J-1161 FOR 24" AND J-1361 FOR 30".
9. AVOID 12" HIGH BARREL SECTIONS




STANDARDS &
SPECIFICATIONS

REVISED:

MANHOLE
RISER

DATE:

DRAWING NO. 300-06



NOTES:

1. MANHOLE SHALL HAVE EITHER CAST-IN-PLACE REINFORCED CONCRETE BASE OR PRECAST BASE.
2. SQUARE BASES ARE ACCEPTABLE (IF APPROVED BY AUTHORITY).
3. SEE STANDARD PLAN FOR SECTIONS A-A AND B-B.




STANDARDS &
SPECIFICATIONS

REVISED:


**MANHOLE
BASE**

DATE:

DRAWING NO. 300-07



SECTION A-A



SECTION B-B
NTS





STANDARDS &
SPECIFICATIONS

REVISED:

**CAST-IN-PLACE
MANHOLE BASE**

DATE:

DRAWING NO. 300-08



*NOTE: 1) PREPOURED INVERTS ARE NOT ALLOWED
2) AVOID 12" BARREL SECTIONS.



STANDARDS &
SPECIFICATIONS

REVISED:

PRECAST CONCRETE
MANHOLE BASE

DATE:

DRAWING NO. 300-09

CAST IRON RING AND COVER
WITH "SEWER" CAST IN

18" MAX.
6"

12"

CONCRETE GRADE RINGS

ECCENTRIC CONE

PRECAST CONCRETE MANHOLE
BARREL SECTIONS (ASTM C478)

MASTIC BETWEEN
JOINTS

5 1/4"

PRECAST MANHOLE
RISER

12"

48", 60", 72" DIA.

GROUT ALL AROUND
INSIDE & OUTSIDE
(TYPICAL)

POURED BASE LEVEL

PVC TEE

PVC

#4 REBAR 12"
O.C. EACH WAY

PVC 90° BEND

CONCRETE AROUND
DROP SECTION ONLY

NOTES:

1. SEE MANHOLE REINFORCEMENT DETAIL FOR BASE.
2. STEPS INSTALLED OVER DOWNSTREAM INVERT OF MANHOLE.

3" CLEAR

8" MIN.

WATERSTOP GASKET

SHAPED INVERTS

CONCRETE (SEE EITHER
CAST-IN-PLACE OR PRECAST
MANHOLE BASE DETAIL




STANDARDS &
SPECIFICATIONS

REVISED:

OUTSIDE DROP
MANHOLE

DATE:

DRAWING NO. 300-10



NOTE:
PROVIDE ONLY IF MANHOLE NOT IN TRAVELED WAY




STANDARDS &
SPECIFICATIONS

REVISED:

MANHOLE MARKER POST


DATE:

DRAWING NO. 300-11



NOTE:
ANY SUBDRAIN UNDER THE SEWER
SHALL BE REPLACED SUCH THAT
NO FLOW SHALL ENTER THE
WATER LINE TRENCH.

SECTION A-A



WITH "D" LESS THAN 2'

SEWER CROSSING
PLAN

NOTE:
ALL EXISTING SEWER DAMAGED DURING INSTALLATION
MUST BE REPLACED WITH PVC PIPE.



STANDARDS &
SPECIFICATIONS

REVISED:

STORM SEWER AND
SANITARY SEWER
CROSSING

DATE:


DRAWING NO. 300-12

A technical diagram of a bellows assembly. It shows a cylindrical bellows with two flange-like ends. Below the bellows, there is a cross-hatched area representing a base or support. Two arrows point from the text "BELL HOLES" to two circular openings in the base, which are aligned with the flange ends of the bellows.

Diagram illustrating a 1/8 bend connection. The bend is shown with a 120° angle, divided into two 30° segments. The connection is labeled "1/8 BEND". The bend is secured with a "CONCRETE COLLAR". The minimum grade is specified as "MIN. GRADE 1/4" PER FT.". The connection is labeled "TAP TO BE MACHINE DRILLED ONLY".

NOTES:


1. BELLS SHALL NOT TOUCH THE SIDES OR BOTTOM OF THE BELL HOLE.
2. THE BARREL SECTION SHALL BE SUPPORTED THROUGHOUT ITS LENGTH.
3. SERVICE TAPS SHALL BE IN-LINE TEE OR MACHINE TAPPED. HAND TAPS SHALL NOT BE ALLOWED.
4. SERVICE LINES SHALL BE LOCATED 5' DOWNHILL FROM CENTERLINE OF THE LOT AND A MINIMUM OF 10' FROM THE WATER SERVICE LINE.
5. THE MIN. SERVICE LINE GRADE SHALL BE 1/4" PER FT.
6. JOINTS SHALL BE WATER TIGHT.
7. WHEN SERVICE STUB-INS ARE INSTALLED WITH THE SEWER MAIN, THEY SHALL BE EXTENDED AT LEAST TO PROPERTY LINE AND SHALL BE PLUGGED WITH A 2x4 MARKER FOR LOCATION OF END.



REVISÉ:

DATE:

DRAWING NO. 300-13



TERMINAL CLEANOUT

NOTES:

NOT A WMD STANDARD DETAIL

SIX INCH PRIVATE SEWERS ONLY!

ACCEPTABLE PIPE TYPES – VCP, PVC, DIP



STANDARDS &
SPECIFICATIONS

REVISED:

**TYPICAL
CLEANOUT**

DATE:

DRAWING NO. 300-14

INCREMENTAL RAINFALL DEPTH/RETURN PERIOD

TIME (MIN)	BASINS LESS THAN 5 SQ MILES					BASINS BETWEEN 5 AND 10 SQ MILES					BASINS BETWEEN 10 AND 20 SQ MILES				
	2 YR (IN)	5 YR (IN)	10 YR (IN)	50 YR (IN)	100 YR (IN)	2 YR (IN)	5 YR (IN)	10 YR (IN)	50 YR (IN)	100 YR (IN)	2 YR (IN)	5 YR (IN)	10 YR (IN)	50 YR (IN)	100 YR (IN)
5	0.02	0.03	0.03	0.03	0.03	0.02	0.03	0.03	0.03	0.03	0.02	0.03	0.03	0.03	0.03
10	0.04	0.05	0.06	0.08	0.08	0.04	0.05	0.06	0.08	0.08	0.04	0.05	0.06	0.08	0.08
15	0.08	0.12	0.14	0.12	0.12	0.08	0.12	0.14	0.12	0.12	0.08	0.12	0.14	0.12	0.12
20	0.16	0.22	0.25	0.19	0.22	0.15	0.21	0.25	0.19	0.22	0.14	0.20	0.25	0.19	0.22
25	0.25	0.36	0.42	0.35	0.38	0.24	0.35	0.40	0.34	0.36	0.23	0.32	0.38	0.32	0.34
30	0.14	0.10	0.20	0.59	0.68	0.13	0.17	0.19	0.57	0.65	0.13	0.16	0.18	0.53	0.61
35	0.06	0.08	0.09	0.28	0.38	0.06	0.08	0.09	0.27	0.36	0.06	0.08	0.09	0.25	0.34
40	0.05	0.06	0.07	0.19	0.22	0.05	0.06	0.07	0.19	0.22	0.05	0.06	0.07	0.19	0.22
45	0.03	0.05	0.06	0.12	0.17	0.03	0.05	0.06	0.12	0.17	0.03	0.05	0.06	0.12	0.17
50	0.03	0.05	0.05	0.12	0.14	0.03	0.05	0.05	0.12	0.14	0.03	0.05	0.05	0.12	0.14
55	0.03	0.04	0.05	0.08	0.11	0.03	0.04	0.05	0.08	0.11	0.03	0.04	0.05	0.08	0.11
60	0.03	0.04	0.05	0.08	0.11	0.03	0.04	0.05	0.08	0.11	0.03	0.04	0.05	0.08	0.11
65	0.03	0.04	0.05	0.08	0.11	0.03	0.04	0.05	0.08	0.11	0.03	0.04	0.05	0.08	0.11
70	0.02	0.04	0.05	0.06	0.05	0.02	0.04	0.05	0.06	0.05	0.02	0.04	0.05	0.06	0.05
75	0.02	0.03	0.05	0.06	0.05	0.02	0.03	0.05	0.06	0.05	0.02	0.03	0.05	0.06	0.05
80	0.02	0.03	0.04	0.04	0.03	0.02	0.03	0.04	0.04	0.03	0.02	0.03	0.04	0.04	0.03
85	0.02	0.03	0.03	0.04	0.03	0.02	0.03	0.03	0.04	0.03	0.02	0.03	0.03	0.04	0.03
90	0.02	0.03	0.03	0.03	0.03	0.02	0.03	0.03	0.03	0.03	0.02	0.03	0.03	0.03	0.03
95	0.02	0.03	0.03	0.03	0.03	0.02	0.03	0.03	0.03	0.03	0.02	0.03	0.03	0.03	0.03
100	0.02	0.02	0.03	0.03	0.03	0.02	0.03	0.03	0.03	0.03	0.02	0.03	0.03	0.03	0.03
105	0.02	0.02	0.03	0.03	0.03	0.02	0.02	0.03	0.03	0.03	0.02	0.02	0.03	0.03	0.03
110	0.02	0.02	0.03	0.03	0.03	0.02	0.02	0.03	0.03	0.03	0.02	0.02	0.03	0.03	0.03
115	0.01	0.02	0.03	0.03	0.03	0.01	0.02	0.03	0.03	0.03	0.01	0.02	0.03	0.03	0.03
120	0.01	0.02	0.02	0.03	0.03	0.01	0.02	0.02	0.03	0.03	0.01	0.02	0.02	0.03	0.03
125											0.01	0.02	0.02	0.02	0.02
130											0.01	0.01	0.02	0.02	0.02
135											0.01	0.02	0.01	0.02	0.02
140											0.01	0.02	0.01	0.02	0.02
145											0.01	0.01	0.01	0.02	0.02
150											0.01	0.01	0.01	0.01	0.02
155											0.01	0.01	0.01	0.01	0.01
160											0.01	0.01	0.01	0.01	0.01
165											0.01	0.01	0.01	0.01	0.01
170											0.01	0.01	0.01	0.01	0.01
175											0.01	0.01	0.01	0.01	0.01
180											0.01	0.01	0.01	0.00	0.00
TOTAL	1.15	1.61	1.89	2.72	3.12	1.12	1.58	1.86	2.60	3.05	1.22	1.68	1.97	2.76	3.14

N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:

DESIGN STORMS

DATE:

DRAWING NO. 400-01



STANDARDS &
SPECIFICATIONS

REVISED:

DATE:

DRAWING NO. 400-02

STORM TIME-INTENSITY- FREQUENCY

N.T.S.

DURATION DURATION FACTORS	5 MIN 0.29	10 MIN 0.45	15 MIN 0.57	30 MIN 0.79	60 MIN 1.00
FREQUENCY	DEPTH (IN)	DEPTH (IN)	DEPTH (IN)	DEPTH (IN)	DEPTH (IN)
2 YR.	0.29	0.45	0.57	0.79	1.00
5 YR	0.41	0.64	0.81	1.12	1.42
10 YR	0.49	0.76	0.96	1.33	1.68
50 YR	0.68	1.06	1.34	1.86	2.35
100 YR	0.79	1.22	1.54	2.14	2.71

NOTE:

1. DEPTH AT EACH DURATION = ONE HOUR RAINFALL DEPTH x RESPECTIVE DURATION
2. SEE FIGURE 400-6 FOR GRAPH OF THESE VALUES

PREPARED BY: _____ DATE: _____

THE DRAINAGE REPORT WITH PLAN DRAWINGS, AS NOTED BELOW HAS BEEN RECEIVED AND FOUND TO LACK THE INFORMATION NOTED. THIS INFORMATION MUST BE SUBMITTED BEFORE THE REPORT WILL BE ACCEPTED FOR REVIEW. PLEASE PROVIDE THE REQUIRED INFORMATION AND RETURN THIS CHECKLIST WITH YOUR SUBMITTAL.

SUBDIVISION: _____

LOCATION: _____

DATE SUBMITTED: _____ TYPE OF REPORT: PRELIM _____ FINAL _____

SUBMITTED BY: FIRM: _____

CONTACT: _____ PHONE: _____

SUBMITTED DATE: (1) _____ (2) _____ (3) _____ (4) _____

DATE APPROVED: _____

CHECKLIST

ITEM	DESCRIPTION	RECEIVED OR NOT APPLICABLE	TO BE SUBMITTED
1.	TYPED, BOUND REPORT	_____	_____
2.	PROFESSIONAL ENGINEERS CERTIFICATE	_____	_____
3.	GENERAL LOCATION AND DESCRIPTION		
	A. LOCATION MAP	_____	_____
	B. EXISTING SITE DESCRIPTION	_____	_____
	C. DESCRIPTION OF EXISTING DRAINAGE PATTERNS AND FACILITIES	_____	_____
4.	DRAINAGE BASINS AND SUB-BASINS		
	A. MAJOR BASIN DESCRIPTION	_____	_____
	B. SUB-BASIN DESCRIPTION	_____	_____
5.	DESIGN CRITERIA		
	A. DEVELOPMENT MASTER PLAN DISCUSSION	_____	_____
	B. HYDROLOGIC CRITERIA DISCUSSION	_____	_____
	C. HYDRAULIC CRITERIA DISCUSSION	_____	_____
6.	DRAINAGE FACILITY DESIGN		
	A. DISCUSSION OF PROPOSED FACILITIES	_____	_____
	B. DISCUSSION OF DRAINAGE PATTERNS	_____	_____
	C. IMPACT ON OFFSITE FACILITIES	_____	_____
	D. IMPACT ON MASTER PLAN	_____	_____
7.	DRAINAGE PLAN		
	A. TOPOGRAPHIC CONTOURS	_____	_____
	B. R.O.W. AND EASEMENTS	_____	_____
	C. DELINEATION OF BASIN AND SUB-BASINS	_____	_____
	D. EXISTING DRAINAGE PATTERNS AND FACILITIES	_____	_____
	E. PROPOSED DRAINAGE PATTERNS AND FACILITIES	_____	_____
	F. PROPOSED OUTFALL POINTS	_____	_____
	G. ROUTING OF OFFSITE DRAINAGE	_____	_____
	H. ROUTING FROM SITE TO MAJOR DRAINAGE WAY	_____	_____

N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:

**DRAINAGE REPORT
SUBMITTAL REPORT**

DATE:

DRAWING NO. 400-03

TIME OF CONCENTRATION

SUBDIVISION _____
CALCULATED BY _____ DATE _____

[illegible]

N.T.S.



STANDARDS & SPECIFICATIONS

REVISÉD:

DESIGN STORMS

DATE:

DRAWING NO. 400-04

STORM DRAINAGE SYSTEM DESIGN (RATIONAL METHOD PROCEDURE)

CALCULATED BY _____ JOB NO _____
 DATE _____ PROJECT _____
 CHECKED BY _____ DESIGN STORM _____

STREET	DESIGN POINT	DIRECT RUNOFF						TOTAL RUNOFF				STREET			PIPE			TRAVEL TIME			REMARKS
		AREA DESIGN (AC)	AREA (AC)	RUNOFF COEFF	t_c MIN	CA (AC)	IN/HR	t_c MIN	CA (AC)	IN/HR	t_c MIN	SLOPE %	STREET SLOPE %	DESIGN FLOW CFS	FLOW CFS	SLOPE %	PIPE SIZE	LENGTH (FT)	VELOCITY (FPS)	t_t (MIN)	
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)	(14)	(15)	(16)	(17)	(18)	(19)	(20)	(21)	(22)
1																					
2																					
3																					
4																					
5																					
6																					
7																					
8																					
9																					
10																					
11																					

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

STORM DRAIN
SYSTEM DESIGN

DATE:


DRAWING NO. 400-05



A=BASIN DESIGNATION

B=AREA IN ACRES

C=COMPOSITE RUNOFF COEFFICIENTS



D=DESIGN POINT DESIGNATION

SUMMARY RUNOFF TABLE (TO BE PLACED ON DRAINAGE PLAN)

DESIGN POINT	CONTRIBUTING AREA (ACRES)	RUNOFF 5YR (CFS)	PEAK 100YR (CFS)
XX	XX.XX	XX.X	XX.X

N.T.S.



STANDARDS &
SPECIFICATIONS


REVISED:

**SYMBOL CRITERIA
AND**

DATE:

DRAWING NO. 400-06

HYDROLOGY TABLE



V_R , PRODUCT OF VELOCITY AND HYDRAULIC RADIUS

NOTE: FROM "HANDBOOK OF CHANNEL DESIGN FOR SOIL AND WATER CONSERVATION," U.S. DEPARTMENT OF AGRICULTURE, SOILS CONSERVATION SERVICE, NO. SCS-TP-61 MARCH, 1947
REVISED JUNE, 1954

N.T.S.



STANDARDS &
SPECIFICATIONS


REVISED:

**ROUGHNESS
COEFFICIENT FOR
GRASS CHANNELS**

DATE:

DRAWING NO. 400-07

TYPE B



NOTE:

1. MAIN CHANNEL: CAPACITY TO BE NO LESS THAN 20% OF 100-YEAR AT MAIN CHANNEL DEPTH. MAXIMUM 100-YEAR FLOW VELOCITY IS 7 FPS.
2. TRICKLE CHANNEL: MINIMUM CAPACITY TO BE 1% TO 3% OF 100-YEAR FLOW BUT NOT LESS THAN 1 CFS. CHANNEL TO BE CONSTRUCTED OF CONCRETE, GROUTED RIPRAP OR OTHER MATERIALS APPROVED BY THE CITY ENGINEER. SEE FIGURE 400-16 FOR REQUIREMENTS IN SANDY SOILS.
3. NORMAL DEPTH: FLOW DEPTH FOR 100-YEAR FLOW SHALL NOT EXCEED 5 FEET.
4. FREEBOARD: FREEBOARD TO BE A MINIMUM OF 1 FOOT.
5. MAINTENANCE ACCESS ROAD: MINIMUM WIDTH TO BE 12 FEET. CITY MAY REQUIRE ALL OR PART OF THE ROAD TO BE SURFACED.
6. EASEMENT/ROW WIDTH: MINIMUM WIDTH TO INCLUDE FREEBOARD AND MAINTENANCE ACCESS ROAD.
7. OVERBANK: FLOW IN EXCESS OF MAIN CHANNEL TO BE CARRIED IN THIS AREA. AREA MAY BE USED FOR RECREATION PURPOSES.

N.T.S.



STANDARDS &
SPECIFICATIONS


REVISED:

DATE:


DRAWING NO. 400-08

**TYPICAL
GRASS LINED
CHANNEL SECTION**


TYPE I



TYPE II



TYPE III



NOTE:

1. SEE FIGURE 400— FOR CAPACITY OF ROADSIDE DITCH.
2. FOR STREET SLOPES GREATER THAN MAXIMUM ALLOWABLE, CHECK DROPS (2' MAXIMUM HEIGHT) WILL BE REQUIRED.

N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:

ROADSIDE DITCH
SECTIONS

DATE:

DRAWING NO. 400-09

	DITCH TYPE I		DITCH TYPE II		DITCH TYPE III	
SLOPE (%)	VEL. (FPS)	Q (CFS)	VEL. (FPS)	Q (CFS)	VEL. (FPS)	Q (CFS)
0.5	1.4	4	2.2	14	4.1	28
1.0	2.5	11	3.3	20	NOT PERMITTED	
1.5	3.4	20	NOT PERMITTED		NOT PERMITTED	
2.0	4.3	26	NOT PERMITTED		NOT PERMITTED	
2.5	5.0	32	NOT PERMITTED		NOT PERMITTED	
3.0 (4)	5.7	37	NOT PERMITTED		NOT PERMITTED	

- NOTES:
1. SEE FIGURE 400-17 FOR GEOMETRY OF ROADSIDE DITCH
 2. VELOCITY IS BASED UPON THE SCS RETARDANCE CURVE "D". SEE FIGURE 400-13.
 3. CAPACITY IS BASED UPON THE SCS RETARDANCE CURVE "C". SEE FIGURE 400-13.
 4. MAXIMUM PERMISSIBLE SLOPE FOR ROADSIDE DITCH IS 3.0%. SLOPE LIMITATION IS BASED ON A MAXIMUM FROUDE NUMBER OF 0.8 FOR TYPE I AND II AND 0.9 FOR TYPE III DITCH.
 5. LINEARLY INTERPOLATE FOR INTERMEDIATE SLOPES.

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

ROADSIDE DITCH CAPACITIES


DATE:

DRAWING NO. 400-10



RECTANGULAR CHANNEL SECTION

NOTE: CONCRETE TO BE REINFORCED WITH FIBERMESH PER MANUFACTURERS SPECIFICATIONS



COMBINATION CHANNEL SECTION

N.T.S.





STANDARDS &
SPECIFICATIONS

REVISED:


TRICKLE CHANNEL
DETAILS

DATE:

DRAWING NO. 400-11



PLAN



PROFILE

SECTION A-A

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

CHANNEL RUNDOWN

DATE:

DRAWING NO. 400-12



N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

NOMOGRAPH FOR FLOW IN TRIANGULAR GUTTERS


DATE:

DRAWING NO. 400-13



REDUCTION FACTOR FOR ALLOWABLE GUTTER CAPACITY WHEN APPROACHING AN ARTERIAL STREET

APPLY REDUCTION FACTOR FOR APPLICABLE SLOPE TO THE THEORETICAL GUTTER CAPACITY TO OBTAIN ALLOWABLE GUTTER CAPACITY APPROACHING ARTERIAL STREET



REDUCTION FACTOR FOR ALLOWABLE GUTTER CAPACITY LOCAL AND COLLECTOR STREETS

N.T.S.



STANDARDS &
SPECIFICATIONS


REVISED:

GUTTER CAPACITY REDUCTION CURVES


DATE:

DRAWING NO. 400-14

MAJOR STORM



(A) SYMMETRICAL STREET SECTION



(B) NON-SYMMETRICAL STREET SECTION

NOTE: FOR NON-SYMMETRICAL STREET SECTION, ADJUST THE TOTAL GUTTER CAPACITY BY REDUCING THE ALLOWABLE GUTTER CAPACITY FOR THE GUTTER WITH THE HIGHER FLOWLINE.

N.T.S.



STANDARDS &
SPECIFICATIONS



REVISED:

**GUTTER CAPACITY
ADJUSTMENT**

DATE:

DRAWING NO. 400-15

SUMP CONDITIONS—ALL INLETS



N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

ALLOWABLE INLET
CAPACITY

DATE:

DRAWING NO. 400-16



LEGEND:

- Q_L = LOCAL RUNOFF FOR DESIGN STORM TRIBUTARY TO DESIGNATE INLET (CFS)
- Q_I = RUNOFF INTERCEPTED BY INLET (CFS)
- Q_{CO} = CARRY OVER RUNOFF PAST INLET (CFS)
- Q_T = TOTAL RUNOFF AT INLET = $Q_L + Q_{CO}$
- Q_P = RUNOFF IN PIPE

SUMMARY OF FLOWS FOR DESIGN EXAMPLE #4

INLET	Q^*	Q_L	Q_{CO}	Q_T	Q_I	Q_{CO}	Q	SEWER	COMMENTS	
NO. 1; 15' TYPE R	—	8.6	8	0	8	6.4	1.6	6.4	INLET ON GRADE	
NO. 2; 10' TYPE R		7.2	4	1.6	5.6	3.7	1.9	10.1	INLET ON GRADE	
NO. 3; 10' TYPE R		—	10.4	8	1.9	9.9	9.9	0	20.0	INLET IN SUMP CONDITION

* MAXIMUM ALLOWABLE INLET CAPACITY AT MAXIMUM ALLOWABLE GUTTER CAPACITY, FROM FIGURE 400-28

N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:

INLET DESIGN EXAMPLES FOR MINOR STORM

DATE:

DRAWING NO. 400-17

VERTICAL DIMENSION
OF PIPE (INCHES)

MAXIMUM ALLOWABLE DISTANCE
BETWEEN MANHOLES AND/OR CLEANOUTS

15 to 36
42 AND LARGER

400 FEET
500 FEET

MINIMUM RADIUS FOR RADIUS PIPE

DIAMETER OF PIPE

RADIUS OF CURVATURE

48" TO 54"
57" TO 72"
78" TO 108"

28.50 FEET
32.00 FEET
38.00 FEET

SHORT RADIUS BENDS SHALL NOT BE USED ON
SEWERS 42 INCHES OR LESS IN DIAMETER

MINIMUM PIPE DIAMETER

TYPE

MINIMUM EQUIVALENT
PIPE DIAMETER

MINIMUM CROSS-
SECTIONAL AREA

MAIN TRUNK
*LATERAL FROM INLET

18 INCHES

1.77 SQ FT

*MINIMUM SIZE OF LATERAL SHALL ALSO BE BASED UPON A WATER
SURFACE INSIDE THE INLET WITH A MINIMUM DISTANCE OF 1 FOOT
BELOW THE GRATE OR THROAT

MANNING'S N-VALUE

SEWER TYPE

CAPACITY CALCULATION

VELOCITY CALCULATION

CONCRETE (NEWER PIPE)
CONCRETE (OLDER PIPE)
CONCRETE (PRELIMINARY
SIZING)
PLASTIC

.013
.015
.015
.011

.011
.012
.012
.009

N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:

**STORM SEWER
ALIGNMENT AND
SIZE CRITERIA**

DATE:


DRAWING NO. 400-18

EXPANSION/CONTRACTION

(a) EXPANSION (K_e)

θ^*	$\frac{D_2}{D_1} = 3$	$\frac{D_2}{D_1} = 1.5$
10	0.17	0.17
20	0.40	0.40
45	0.86	1.06
60	1.02	1.21
90	1.06	1.14
120	1.04	1.07
180	1.00	1.00

* THE ANGLE θ IS THE ANGLE IN DEGREES BETWEEN THE SIDES OF THE TAPERING SECTION



(b) PIPE ENTRANCE FROM RESERVOIR


BELL-MOUTH $H_L = 0.04 \frac{v^2}{2g}$

SQUARE EDGE $H_L = 0.5 \frac{v^2}{2g}$

GROOVE END U/S FOR CONCRETE PIPE $H_L = 0.2 \frac{v^2}{2g}$

(c) CONTRACTION (K_c)

$\frac{D_2}{D_1}$	K_c
0	0.5
0.4	0.4
0.6	0.3
0.8	0.1
1.0	0



N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:

**STORM SEWER
ENERGY LOSS
COEFFICIENT**

DATE:

DRAWING NO. 400-19

BENDS

$$H_L = K (V_j^2 / 2g)$$


CASE I

CONDUIT ON 90° CURVES

NOTE: HEAD LOSS APPLIED AT PC FOR LENGTH

RADIUS	K_b
1 X D	0.50
(2 TO 8) X D	0.25
(8 TO 20) X D	0.04
>20 X D	0

*WHEN CURVES OTHER THAN 90° ARE USED, APPLY THE FOLLOWING FACTORS TO 90° CURVES
 60° CURVE 85%
 45° CURVE 70%
 22-1/2° CURVE 40%




CASE II

BENDS WHERE RADIUS IS EQUAL TO DIAMETER OF PIPE

NOTE: HEAD LOSS APPLIED AT BEGINNING OF BEND

θ° BEND	K_b
90	0.50
60	0.43
45	0.35
22-1/2	0.20



N.T.S.



STANDARDS &
SPECIFICATIONS



REVISED:

**STORM SEWER
ENERGY LOSS
COEFFICIENT**

DATE:

DRAWING NO. 400-20

BENDS AT MANHOLES



NOTE: HEAD LOSS APPLIED AT OUTLET OF MANHOLE

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:


**STORM SEWER
ENERGY LOSS
COEFFICIENT**

DATE:


DRAWING NO. 400-21




USE EQUATION 400-4
 $K_j = 0.05$



CASE I
 INLET OR STRAIGHT THROUGH
 MANHOLE ON MAIN LINE




USE EQUATION 400-8
 $K_j = 0.25$




CASE II
 INLET ON MAIN LINE
 WITH BRANCH LATERAL


CASE III	
θ°	K_j
22-1/2	0.75
45	0.50
60	0.35
90	0.25
NO LATERAL	SEE CASE I




USE EQUATION 400-8



CASE III
 MANHOLE ON MAIN LINE
 WITH θ° BRANCH LATERAL



USE EQUATION 400-4
 $K_j = 1.25$



CASE IV
 INLET OR MANHOLE AT
 BEGINNING OF LINE

N.T.S.




STANDARDS &
 SPECIFICATIONS

REVISED:

DATE:

DRAWING NO. 400-22

MANHOLE
 JUNCTION LOSSES



N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:


HYDRAULIC PROPERTIES CIRCULAR PIPE

DATE:

DRAWING NO. 400-23

CULVERT RATING

PROJECT _____ LOCATION _____ STATION _____



CULVERT DATA

TYPE _____ n _____

INLET _____ Q FULL _____

K_e _____ V_{FULL} _____

OUTLET CONTROL EQUATIONS

$$(1) \quad H_w = H + h_o - LS_o$$

(2) FOR $T_w < D$; $h_o = \frac{d_c + D}{2}$ OR T_w (WHICHEVER IS GREATER)

$$T_W > D; h_O = T_W$$

(3) FOR BOX CULVERT: $d_c = 0.315(Q/B)^{2/3} \leq D$

[illegible]

N.T.S.




STANDARDS & SPECIFICATIONS

REVISÉD:


CULVERT RATING

DATE:

DRAWING NO. 400-24




SECTION-BASIN FLOOR



SET BACK SILL SECTION TO ALLOW BASIN DRAINAGE

END SILL

$$\begin{aligned} H &= 3w/d \\ L &= 4w/3 \\ a &= w/2 \\ b &= 3w/8 \\ c &= w/2 \\ d &= w/6 \\ t &= w/12 \end{aligned}$$



PROJECTED PIPE AREA IMPACTS BAFFLE SURFACE


ALWAYS ALIGN CLEANOUT NOTCHES IN BAFFLE AWAY FROM THE PROJECTED PIPE AREA

END VIEW-BAFFLE NOTCHES

FOR TWO PIPES OF EQUAL SIZE AND SIMILAR FLOW RATE

$$W_2 = 1.5 W_1$$

W_1 FROM DETAIL 400-52
BASED ON HIGHER FLOW OF D_1 OR D_2



WIDTH ADJUSTMENT FOR DOUBLE PIPE OUTLET

N.T.S.



STANDARDS &
SPECIFICATIONS


REVISED:

**IMPACT STILLING
BASIN**

DATE:

DRAWING NO. 400-25

SHAPE	COEFFICIENT	COMMENTS	SCHEMATIC
SHARP CRESTED	—		
PROJECTION RATIO ($H/P = 0.4$)	3.4	$H < 1.0$	
PROJECTION RATIO ($H/P = 2.0$)	4.0	$H > 1.0$	
BROAD CRESTED	—		
W/SHARP U/S CORNER	2.6	MINIMUM VALUE	
W/ROUNDED U/S CORNER	3.1	CRITICAL DEPTH	
TRIANGULAR SECTION	—		
A) VERTICAL SLOPE	—		
1:1 D/S SLOPE	3.8	$H > 0.7$	
4:1 D/S SLOPE	3.2	$H > 0.7$	
10:1 D/S SLOPE	2.9	$H > 0.7$	
B) 1:1 U/S SLOPE	—		
1:1 D/S SLOPE	3.8	$H > 0.5$	
3:1 D/S SLOPE	3.5	$H > 0.5$	
TRAPEZOIDAL SECTION	—		
1:1 U/S SLOPE, 2:1 D/S SLOPE	3.4	$H > 1.0$	
2:1 U/S SLOPE, 2:1 D/S SLOPE	3.4	$H > 1.0$	
ROAD CROSSINGS	—		
GRAVEL	3.0	$H > 1.0$	
PAVED	3.1	$H > 1.0$	



ADJUSTMENT FOR TAILWATER

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:


**WEIR FLOW
COEFFICIENTS**

DATE:

DRAWING NO. 400-26



TYPE 1 OUTLET



TYPE 2 OUTLET

N.T.S.



STANDARDS &
SPECIFICATIONS


REVISED:

**DETENTION POND
OUTLET
CONFIGURATIONS**

DATE:


DRAWING NO. 400-27

(A) ORIFICE PLATE DETAILS



NOTE: TRASHRACK CAPACITY TO BE 10 TIMES ORIFICE CAPACITY

(B) TRASHRACK AREA REQUIREMENTS



NOTE:
FOR ORIFICE DIAMETER LESS THAN 3", USE A MINIMUM CLEAR OPENING OF 2 FT²

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**DETENTION POND
DETAILS**


DATE:

DRAWING NO. 400-28



ANCHOR
TRENCH



SECTION THROUGH
FILTER POINT MAT



SECTION THROUGH
UNIFORM CROSS
SECTION MAT

8 INCH FILTER POINT

UNIFORM CROSS SECTION



NOTE:

1. NUMBERS REFER TO SEQUENCE OF MORTAR INJECTION
2. LINERS MAY BE USED PROVIDED THE FROUDE NUMBER OF THE CHANNEL SECTION IS LESS THAN 0.8

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:


**EROSION CONTROL
MATTRESSES**

DATE:


DRAWING NO. 400-29



REINFORCED CONCRETE PIPE (RCP)



POLYVINYL CHLORIDE PIPE (PVC)



HIGH DENSITY POLYETHYLENE (HDPE) CORRUGATED METAL PIPE (CMP)

NATIVE SOIL:	BEDDING:
COARSE GRAINED SAND AND GRAVEL (50% OR MORE BY WEIGHT RETAINED ON # 40 SIEVE)	CDOT CLASS A FILTER MATERIAL (SECTION 703.0q)
FINE GRAINED SOIL (LESS THAN 50% RETAINED ON # 40 SIEVE)	UDFCD TYPE 1 FILTER MATERIAL, CDOT FINE AGGREGATE FOR CONCRETE AASHTO M6 (SECTION 703.01)

* MINIMUM COVER SHALL NOT INCLUDE PAVEMENT.

** MAY BE REQUIRED IN AREAS WITH HIGH GROUNDWATER TABLE OR UNSUITABLE SUB-GRADE.

N.T.S.






STANDARDS &
SPECIFICATIONS

REVISED:


**STORM DRAINAGE
PIPE BEDDING
DETAILS**

DATE:

DRAWING NO. 400-30



MULTIPLE CHASE



N.T.S.





STANDARDS &
SPECIFICATIONS

REVISED:

**CHASE DRAIN
DETAILS**

DATE:

DRAWING NO. 400-31



N.T.S.






STANDARDS &
SPECIFICATIONS

REVISED:

**UNDERDRAIN
CLEANOUT
DETAIL**

DATE:

DRAWING NO. 400-32



NOTES:

1. JOINTS TO BE SET IN FLEXIBLE BUTYL RESIN SEALING COMPOUND AND GROUTED WITH MORTAR INSIDE AND OUTSIDE.
2. BASES SHALL BE REINFORCED WHEN THE DISTANCE FROM INVERT TO TOP OF COVER WILL EXCEED 15 FT. REINFORCING TO BE APPROVED BY CITY ENGINEER.
3. SQUARE BASES ARE ACCEPTABLE.
4. FOR PIPE 36" AND LARGER, OR WHERE CONDITIONS SUCH AS MULTIPLE PIPES WARRANT, A CONCRETE BOX BASE WILL BE REQUIRED.
(SEE CDOT STANDARD DRAWING M-604-20)

N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:


**STANDARD MANHOLE
BASE**

DATE:


DRAWING NO. 400-33

NOTES:


1. ALL JOINTS TO BE SET IN FLEXIBLE BUTYL RESIN SEALING COMPOUND AND PLASTERED WITH MORTAR 5/8" THICK AND EXTENDING 4" EACH SIDE OF JOINT INSIDE AND OUTSIDE.
2. MORTAR ON RISER RINGS IS ACCEPTABLE.
3. MANHOLES INSTALLED OUTSIDE OF STREET RIGHT-OF-WAY SHALL HAVE LOCKING COVERS.
4. "SEWER" TO BE IMPRINTED ON COVER.
5. FOR PIPE 36" AND LARGER, OR WHERE CONDITIONS SUCH AS MULTIPLE PIPES WARRANT, A CONCRETE BOX BASE WILL BE REQUIRED.
(SEE CDOT STANDARD DRAWING M-604-20)



**TYPICAL MANHOLE SECTION
WITH ECCENTRIC CONE**



PLAN



ALTERNATE FLAT TOP

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**MANHOLE BARRELS
AND
ALTERNATE TOPS**

DATE:

DRAWING NO. 400-34



FOR MANHOLES
OVER 17' IN DEPTH

N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:

INTERMEDIATE
PLATFORM

DATE:

DRAWING NO. 400-35

REQUIRED WHEN $L=4.5$ m AND $H>2$ m

36" 6'-4" 8" $L=5'$ 5 1/2" o.c.

11'-4" $L=10'$

16'-4" $L=15'$ 8" 36"

601

409 503

3 Rods In 10' Inlet

5 Rods In 15' Inlet

18" 30" 30" 30"

One 1 1/4" dia. Rod in 5' Inlet

3" clr

3" Each end

TRANSITION GUTTER


Face of Curb

* WHEN A TYPE R INLET IS USED WITH MOUNTABLE CURB AND GUTTER, 1.5 m TRANSITION SHALL BE REQUIRED.

* CURB AND GUTTER HERE.

DIRECTION OF FLOW

TYPICAL PLAN VIEW




N.T.S.



REVISÉ:


DATE:

DRAWING NO. 400-36




TRANSITION CURB


MEET SHAPE OF NORMAL BARRIER



▼ CURB FACE ASSEMBLY, PLACE ENTIRE ASSEMBLY BEFORE POURING CONCRETE



(DOTTED BARS ARE IN SECTION d-d)
SECTIONS c-c & d-d



SECTION B-B TYPICAL END VIEW

NOTE: MANHOLE RING & COVER, STATION POINT AND OUTFLOW PIPE SHALL BE LOCATED AT THE SAME END OF THE INLET.

N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:

CURB INLET TYPE R
SHEET 2 OF 4

DATE:

DRAWING NO. 400-37

TABLE ONE ~ BAR LIST FOR CURB INLETS, TYPE "R"

MARK	DIA (in)	O.C. SPACING (in)	TYPE	ALL INLETS		INLETS, H ≤ 5'				INLETS, H > 5'			
				L= 5'		10'		15'		10'		15'	
				NO. REQ'D.	LENGTH (ft-in)	NO. REQ'D.	LENGTH (ft-in)	NO. REQ'D.	LENGTH (ft-in)	NO. REQ'D.	LENGTH (ft-in)	NO. REQ'D.	LENGTH (ft-in)
401	↑	11"	II	15	*	21	*	26	*	11	*	11	*
402		11"	II	7	*	13	*	18	*	7	*	7	*
403		9"	II	*	4'-0"	*	4'-0"	*	4'-0"	*	4'-0"	*	4'-0"
405		6"	VI	11	6'-10"	21	6'-10"	31	6'-10"	11	6'-10"	11	6'-10"
406		6"	VIII	7	8'-10"	7	13'-10"	7	18'-10"	7	8'-10"	7	8'-10"
407	1/2"	9"	II	*	5'-10"	*	10'-10"	*	15'-10"	*	5'-10"	*	5'-10"
408		12"	II	3	6'-0"	3	11'-0"	3	16'-0"	3	11'-0"	3	16'-0"
409		8"	II	6	5'-10"	6	10'-10"	6	15'-10"	6	10'-10"	6	15'-10"
410		11"	VI							3	*	3	*
411		11"	II							3	5'-2"	3	10'-2"
412		11"	II							3	2'-9"	3	2'-9"
413	↓	9"	II							7	10'-10"	7	15'-10"
501	↑	5 1/2"	IV	11	3'-4"	22	3'-4"	33	3'-4"	22	3'-4"	33	3'-4"
502	5/8"	5 1/2"	III							11	11'-5"	17	11'-5"
503		5 1/2"	II	5	3'-6"	16	3'-6"	27	3'-6"	6	3'-6"	6	3'-6"
504	↓	5 1/2"	IX									5	8'-4"
601	3/4"	2 1/2"	V	2	8'-10"	2	8'-10"	2	8'-10"	2	8'-10"	4	8'-10"
Ø8[8.5				1	5'-10"	1	10'-10"	1	15'-10"	1	10'-10"	1	15'-10"
▼				2 BARS, 1 ROD		4 BARS, 3 RODS		8 BARS, 5 RODS		4 BARS, 3 RODS		8 BARS, 5 RODS	

* VARIABLE, REFER TO TABLE TWO.

Ø INCLUDE 18" NO. 4 BARS (SEE CHANNEL LAYOUT DETAIL).

▼ SEE CURB FACE ASSEMBLY ON SHEET 2 AND CHANNEL LAYOUT DETAILS ON SHEET 4.

REGULAR
INLETS

DROP BOX
INLETS

TABLE TWO ~ BARS AND QUANTITIES VARIABLE WITH "H"


"H" (ft-in)	LENGTH (ft-in)			NO. REQ'D. REGULAR		NO. REQ'D. DROP BOX		L= 5'		L= 10'		L= 15'	
	401	402	410	403	407	403	407						
								CONC. CU.YD.	STEEL LBS.	CONC. CU.YD.	STEEL LBS.	CONC. CU.YD.	STEEL LBS.
3'-0"	2'-8"	1'-8"		10	7			3.2	285	5.3	497	7.4	706
3'-6"	3'-2"	2'-2"		10	7			3.4	305	5.7	528	7.9	747
4'-0"	3'-8"	2'-8"		12	9			3.7	326	6.0	559	8.4	786
4'-6"	4'-2"	3'-2"		12	9			3.9	334	6.4	571	8.8	803
5'-0"	4'-8"	3'-8"		14	11			4.1	354	6.7	602	9.3	844
5'-6"	5'-2"	4'-2"	3'-5"	16	13	15	6	4.4	375	6.0	607	7.4	850
6'-0"	5'-8"	4'-8"	3'-11"	16	13	16	6	4.6	382	6.2	616	7.6	860
6'-6"	6'-2"	5'-2"	4'-5"	18	15	18	8	4.8	402	6.4	637	7.8	880
7'-0"	6'-8"	5'-8"	4'-11"	20	17	19	10	5.0	423	6.6	654	8.0	897
7'-6"	7'-2"	6'-2"	5'-5"	20	17	20	10	5.3	430	6.9	664	8.3	907
8'-0"	7'-8"	6'-8"	5'-11"	22	19	22	12	5.5	451	7.1	684	8.5	927
8'-6"	8'-2"	7'-2"	6'-5"	24	21	23	14	5.7	471	7.3	702	8.7	944
9'-0"	8'-8"	7'-8"	6'-11"	24	21	24	14	6.0	479	7.6	711	9.0	954
9'-6"	9'-2"	8'-2"	7'-5"	26	23	26	16	6.2	499	7.8	732	9.2	974
10'-0"	9'-8"	8'-8"	7'-11"	28	25	27	18	6.4	520	8.0	749	9.4	992
10'-6"	10'-2"	9'-2"	8'-5"	28	25	28	18	6.7	527	8.3	759	9.7	1001
11'-0"	10'-8"	9'-8"	8'-11"	30	27	30	20	6.9	547	8.5	779	9.9	1022

NOTE: FOR L= 5',
L= 10' AND L= 15'

REGULAR INLETS:
TOTAL QUANTITIES NEEDED
ARE OUTSIDE OF THE
HEAVY BLACK LINE.

DROP BOX INLETS:
TOTAL QUANTITIES NEEDED
ARE INSIDE OF THE
HEAVY BLACK LINE.

STEEL WEIGHTS DO NOT
INCLUDE STRUCTURAL
STEEL.



BAR BENDING DIAGRAMS ~ (Dimensions are Out-to-Out of bar)

N.T.S.





STANDARDS &
SPECIFICATIONS

REVISED:

CURB INLET TYPE R
SHEET 3 OF 4


DATE:

DRAWING NO. 400-38




TOP OF COVER

BOTTOM OF COVER



SECTION OF COVER



PICKSLOT DETAIL

COVER: GRAY IRON ASTM A48 CL35 B
 LOAD RATING: H-20
 COVER: 135 LBS 61kg
 PRODUCT NUMBER 00240562
 ✓ MACHINED SURFACE
 EAST JORDAN IRON WORKS #2405A
 PRODUCT #240562

N.T.S.




STANDARDS &
 SPECIFICATIONS

REVISED:

**STORM SEWER
 MANHOLE LID**

DATE:

DRAWING NO. 400-39




STORM OR SANITARY SEWER CROSSING UNDER WATER MAIN

IF $d_3 > 18"$, ENCASEMENT NOT REQUIRED

NOTES:

1. CONCRETE COLLAR AROUND STORM SEWER JOINTS MAY BE ACCEPTED WITH WRITTEN APPROVAL BY THE CITY ENGINEER AND ONLY FOR PIPE 30" OR LARGER.
2. CONCRETE TO BE CAST AGAINST UNDISTURBED SOIL OR SHORING.
3. LENGTH OF ENCASEMENT SHALL EXTEND AT LEAST 10- FEET EACH SIDE OF WATER MAIN.
4. UNLESS OTHERWISE NOTED ON PLAN/PROFILE DRAWINGS, ENCASEMENTS NEED NOT BE REINFORCED.
5. FILLER MATERIAL BETWEEN CONDUITS TO BE:
 - a) APPROVED COMPRESSIBLE MATERIAL SUCH AS STYROFOAM, ETC. IF $d_4 \leq 6"$.
 - b) COMPACTED BACKFILL, IF $d_4 > 6"$.
6. SHORING OR SHEETING, IF USED, TO BE CUT OFF AT TOP OF ENCASEMENT



STORM OR SANITARY SEWER CROSSING OVER TOP OF WATER MAIN

ENCASEMENT REQUIRED REGARDLESS OF DIMENSION d_3
(SEE NOTE 1 FOR SPECIAL CASES)

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**ENCASEMENT FOR
CONDUIT CROSSINGS**

DATE:

DRAWING NO. 400-40



N.T.S.





STANDARDS &
SPECIFICATIONS

REVISED:

**LOCAL ROAD
TYPE I (GRAVEL)**

DATE:

DRAWING NO. 500-01



N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

LOCAL ROAD
TYPE II

DATE:

DRAWING NO. 500-02



N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**LOCAL ROAD
TYPE III**

DATE:

DRAWING NO. 500-03



N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**LOCAL ROAD TYPE IV
COMMERCIAL AND
INDUSTRIAL**

DATE:

DRAWING NO. 500-04



N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**MINOR COLLECTOR
60' ROW**

DATE:

DRAWING NO. 500-05



N.T.S.





STANDARDS &
SPECIFICATIONS

REVISED:

**MAJOR COLLECTOR
90' ROW**

DATE:

DRAWING NO. 500-06




STANDARDS &
SPECIFICATIONS

REVISED:


MINOR ARTERIAL

DATE:


DRAWING NO. 500-07



MAJOR ARTERIAL
4 LANE



MAJOR ARTERIAL
4 LANE W/ACCEL/DECEL LANES



MAJOR ARTERIAL
4 LANE W/TURN LANES

N.T.S.





STANDARDS &
SPECIFICATIONS

REVISED:

MAJOR ARTERIAL

DATE:

DRAWING NO. 500-08



DESIGN SPEED OF THRU ROADWAY (MPH)	MINIMUM SIGHT DISTANCE FOR STOPPED VEHICLE (FT.)	GRADE CORRECTION DISTANCE (FT.)					
		SPEED	UPGRADE TO		FOR DOWNGRADES		
25	250		3%	6%	3%	6%	
30	300	25	0	-10	+10	+20	
		30	0	-10	+10	+20	
35	350	35	-10	-15	+10	+25	
		40	-10	-20	+10	+30	
40	400	45	-15	-25	+15	+40	
45	450						

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:


SIGHT DISTANCE

DATE:


DRAWING NO. 500-10



LOCAL-LOW VOLUME



LOCAL-STANDARD RESIDENTIAL



LOCAL-STANDARD COMMERCIAL/INDUSTRIAL

NOTE: THESE STANDARDS MAY BE APPLIED TO ASYMMETRICAL CUL-DE-SACS.

- DESIGN ENGINEER SHOW REFERENCE ELEVATIONS AT THESE POINTS.

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**CUL-DE-SAC
DETAIL**

DATE:

DRAWING NO. 500-11



N.T.S.



STANDARDS &
SPECIFICATIONS


REVISED:

**HAMMERHEAD
CUL-DE-SAC**


DATE:

DRAWING NO. 500-12


0.5" EXPANSION JOINT MATERIAL
AT EACH END OF ALL CURB RETURNS
AND AT 150 FEET MAX. SPACING




LAYOUT




EXPANSION JOINT



CONTRACTION JOINT



6" VERTICAL CURB & GUTTER



6" VERTICAL MEDIAN CURB & GUTTER

NOTES:

- EXPANSION JOINT MATERIAL SHALL BE NON-EXTRUDING AND RESILIENT TYPE TO MEET AASHO SPEC. M-213.
- ANY OVER-EXCAVATION SHALL BE REPLACED WITH GRANULAR BACKFILL COMPACTED TO 95% MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D-698.
- TYPE 2 SPILL CURB MAY BE REQUIRED FOR SPECIAL CONDITIONS.
- ④ GUTTER CROSS SLOPE SHALL BE 1/2" /FT. WHEN DRAINING AWAY FROM CURB AND 1" /FT. WHEN DRAINING TOWARD CURB.
- TYPE 2 CURB & GUTTER IS FOR USE IN COMMERCIAL, ARTERIALS AND COLLECTOR STREETS.

LEGEND FOR RADII	
A	= 1/8" TO 1/4"
B	= 1"
C	= 1-1/2"
D	= 1-1/2" TO 2"

N.T.S.





STANDARDS &
SPECIFICATIONS

REVISED:

6" VERTICAL CURB AND GUTTER

DATE:

DRAWING NO. 500-13



NOTES:

1. EXPANSION JOINT MATERIAL SHALL BE NON-EXTRUDING AND RESILIENT TYPE TO MEET AASHO SPEC. M-213.
2. ANY OVER-EXCAVATION SHALL BE REPLACED WITH GRANULAR BACKFILL COMPACTED TO 95% MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D-698.

N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:

**4" MOUNTABLE
CURB, GUTTER
AND WALK**


DATE:

DRAWING NO. 500-14




CROSS PAN
INDUSTRIAL/ARTERIAL/
COLLECTOR STREET

DRAWING NO. 500-15



COMBINATION CURB, GUTTER
& SIDEWALK TYPE 1



SECTION A-A

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**CROSS PAN
LOCAL STREET**

DATE:

DRAWING NO. 500-16



N.T.S.





STANDARDS &
SPECIFICATIONS

REVISED:


**COMBINATION CURB,
GUTTER AND
SIDEWALK**

DATE:

DRAWING NO. 500-17



**SECTION
A'-A**



**SECTION
B-B**

N.T.S.





STANDARDS &
SPECIFICATIONS

REVISED:

**VERT. CURB, GUTTER,
ATTACHED SIDEWALK**

DATE:

DRAWING NO. 500-18



SECTION A'-A

NOTES:

1. HORIZONTAL GEOMETRY OF THE BACK OF WALK VARIES DEPENDING ON THE CURB RADIUS AND PRE-EXISTING PHYSICAL OBSTRUCTIONS. THE DESIGN SHALL ADEQUATELY PROVIDE A MINIMUM WIDTH ROUTE BEHIND THE RAMP WITH AN AESTHETICALLY PLEASING APPEARANCE.
2. 1/2" WIDE X 1/2" DEEP GROOVES SHALL BE SPACED AT 12"
3. THE RAMP AND WINGS SHALL BE TEXTURED WITH A COARSE BROOMED FINISH.
N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**VERT. CURB, GUTTER,
ATTACHED SIDEWALK**

DATE:

DRAWING NO. 500-19



N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

DRIVEWAY APRON LOCAL STREET

DATE:

DRAWING NO. 500-20



N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:


**DRIVEWAY APRON
ARTERIAL/COLLECTOR
STREET**

DATE:


DRAWING NO. 500-21



PLAN



THICKENED EDGE



SECTION A-A

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:


**CONCRETE BUS
PAD**

DATE:


DRAWING NO. 500-22



SUBBASE MATERIAL CARRIED THROUGH SHOULDER



SUBBASE MATERIAL NOT CARRIED THROUGH SHOULDER



CURB AND GUTTER SECTION

NOTE: WHERE THE BOTTOM OF SELECT MATERIAL IS GREATER THAN 4'-0" BELOW PAVEMENT, THE UNDERDRAIN PIPE IS TO BE COINCIDENT WITH THE BOTTOM OF SELECT MATERIAL, AND THE TRENCH DEPTH AND BACKFILL QUANTITY INCREASED ACCORDINGLY.

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:


STANDARD PIPE
UNDERDRAINS

DATE:

DRAWING NO. 500-23



WITHOUT SUBSURFACE MATERIAL



WITH SUBSURFACE MATERIAL

N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**PIPE UNDERDRAIN
FOR RAISED
IRRIGATED MEDIANS**


DATE:

DRAWING NO. 500-24



PROVIDE A 1" MOUND AROUND EACH POST TO DRAIN AWAY FROM POST

SUBGRADE



SUBGRADE

12" DIA. CONCRETE PIER

NOTE: PICKETS SHOULD ABUTT AGAINST EACH OTHER.

FRONT VIEW

SIDE VIEW

N.T.S.



STANDARDS &
SPECIFICATIONS

REVISED:

SOUND BARRIER FENCE


DATE:

DRAWING NO. 500-25

NOTES:

1) A STRUCTURAL ENGINEERING DESIGN FOR THE WALL AND FOUNDATION SHALL BE SUBMITTED TO THE CITY FOR APPROVAL.

2) COLORS FOR SPLIT CONCRETE BLOCKS SHALL BE LIMITED TO:
BROWN # 277, TAN # 276, RED # 265
AS MANUFACTURED BY THREE-COOPER OR APPROVED EQUAL.



N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

**CONCRETE BLOCK
SOUND WALL**

DATE:





DRAWING NO. 500-26



SIDEWALK UNDERDRAINS SHOULD BE TIED INTO THE STORM SEWER SYSTEM AT POINTS ABOUT A CITY BLOCK APART. UNDERDRAIN RUNS MUST NOT EXCEED 1,000 FEET IN LENGTH WITHOUT DISCHARGING INTO THE STORM DRAIN SYSTEM OR INTO AN OPEN DRAIN. THE LENGTH OF RUN MAY BE INCREASED UP TO AN ADDITIONAL 1,000 FEET IF 8" DIAMETER PIPE IS USED IN THE DOWNSTREAM 1,000 FEET SECTION OF THE RUN.

STANDARD SIDEWALK UNDERDRAIN

DRAWING NO. 500-27



NOTE: ALL BOXES AND
LIDS MUST BE CAST IRON




STANDARDS &
SPECIFICATIONS

REVISED:

SCREW TYPE
ADJUSTABLE
MONUMENT BOX

DATE:

DRAWING NO. 500-28



SECTION A-A



STANDARDS &
SPECIFICATIONS

REVISED:

**HINGED TYPE
ALUMINUM
MONUMENT BOX**

DATE:

DRAWING NO. 500-29




STANDARDS & SPECIFICATIONS

REVISED:


SURVEY MONUMENTS SHEET 2 OF 2

DATE:


DRAWING NO. 500-31



TYPE 4 MONUMENT




TYPE 5 MONUMENT




TYPE 3A MONUMENT,
ROADWAY INSTALLATION

SECTION B-B
2-1/2\"/>


SECTION C-C
6\"/>




TYPE 2 MONUMENT



SECTION A-A














TYPE 1 MONUMENT TYPE 1A MONUMENT & TYPE 2A MONUMENT
INCLUDES MONUMENT BOX



TYPE 3 MONUMENT

DIMENSIONS ARE INCHES (")
UNLESS OTHERWISE NOTED.

BMP LEGEND

	(CD) CHECK DAM
	(CF) CONSTRUCTION FENCE
	(DD) DIVERSION DITCH
	(IP) INLET PROTECTION
	(SB) SEDIMENT BASIN
	(ST) SEDIMENT TRAP
	(SM) SEEDING AND MULCHING
	(SF) SILT FENCE
	(VTC) VEHICLE TRACKING CONTROL
	(STB) STRAW BALE BARRIER
	(LOC) LIMITS OF CONSTRUCTION




STANDARDS &
SPECIFICATIONS

REVISED:

EROSION AND SEDIMENT CONTROL LEGEND

DATE:

DRAWING NO. 600-01



CD


CHECK DAM

Definition

Small temporary dam constructed across a swale or drainage ditch.

Purposes

To reduce the velocity of stormwater flows and erosion of the swale or ditch.



N.T.S.




STANDARDS &
SPECIFICATIONS

REVISED:

CHECK DAM
DETAIL




DATE:

DRAWING NO. 600-02



CF

CONSTRUCTION FENCE





STANDARDS &
SPECIFICATIONS

REVISED:

CONSTRUCTION
FENCE

DATE:

DRAWING NO. 600-03




TEMPORARY DIVERSION DITCH

DEFINITION

A TEMPORARY RIDGE OF COMPACTED SOIL LOCATED AT THE TOP, MIDSLOPE, OR BASE OF A DISTURBED AREA

PURPOSE

1. TO DIVERT STORM RUNOFF FROM HIGHER DRAINAGE AREAS AWAY FROM THE UNPROTECTED SLOPES TO A PERMANENT CHANNEL OR TEMPORARY CHANNEL DIVERSION.
2. TO DIVERT SEDIMENT-LADEN RUNOFF FROM THE MIDSLOPE OF A DISTURBED AREA TO A TEMPORARY SLOPE DRAIN.
3. TO DIVERT SEDIMENT-LADEN RUNOFF FROM THE BASE OF A DISTURBED AREA TO A SEDIMENT TRAPPING FACILITY.



9-1-99

URBAN DRAINAGE AND FLOOD CONTROL DISTRICT




STANDARDS &
SPECIFICATIONS

REVISED:

**TEMPORARY
DIVERSION DITCH**

DATE:

DRAWING NO. 600-04



INLET PROTECTION




Definition

A sediment filter or an excavated impounding area around a storm drain drop inlet or curb inlet.

Purposes

To reduce sediment from entering storm drainage systems prior to permanent stabilization of disturbed areas.




STANDARDS &
SPECIFICATIONS

REVISED:

INLET PROTECTION
DETAIL

DATE:

DRAWING NO. 600-05



INLET PROTECTION




Definition

A sediment filter or an excavated impounding area around a storm drain or curb inlet.

Purposes

To reduce sediment from entering storm drainage systems prior to permanent stabilization of disturbed area.




STANDARDS &
SPECIFICATIONS

REVISED:

INLET PROTECTION
DETAIL

DATE:

DRAWING NO. 600-06



ST

TEMPORARY SEDIMENT TRAP


Definition

A small temporary ponding area, formed by constructing an earthen embankment with a rock-covered outlet across a drainage swale, or by excavation of a depression below original grade. Relative elevations should contain all runoff within the trap area.


Purposes

To detain sediment-laden runoff from disturbed areas long enough to allow the majority of the sediment to settle out.

EXCAVATED SEDIMENT TRAP



EMBANKMENT SEDIMENT TRAP



Rock Lining: 9" thick layer of 6" rock on 3" thick layer of 1/2"-3/4" filter




STANDARDS &
SPECIFICATIONS

REVISED:

TEMPORARY
SEDIMENT TRAP

DATE:

DRAWING NO. 600-07



SB

TEMPORARY SEDIMENT BASIN

DEFINITION

A TEMPORARY BASIN WITH A CONTROLLED STORM WATER RELEASE STRUCTURE, FORMED BY EXCAVATION OR CONSTRUCTION OF AN EMBANKMENT OF COMPACTED SOIL. REQUIRED FOR ALL DRAINAGE AREAS GREATER THAN 1 ACRE.

PURPOSE


TO DETAIN SEDIMENT-LADEN RUNOFF FROM DISTRIBUTED AREAS TO ALLOW THE MAJORITY OF THE SEDIMENT TO SETTLE OUT.

LIMITING GEOMETRY:
L/W GREATER THAN 2.0

REQUIRED VOLUME TO CREST OF
EMERGENCY SPILLWAY = 1800
CUBIC FEET PER ACRE OF
DRAINAGE AREA. SHOULD BE
CLEANED OUT PRIOR TO
BECOMING HALF FULL.

100-YEAR OR LARGER EMERGENCY SPILLWAY

EMERGENCY
SPILLWAY
SHOULD NOT BE
CONSTRUCTED
OVER FILL
MATERIAL



STANDARDS &
SPECIFICATIONS

REVISED:



TEMPORARY
SEDIMENT BASIN

DATE:

DRAWING NO. 600-08

SB

TEMPORARY SEDIMENT BASIN OUTLET DETAIL B



RISER PIPE DETAIL



STANDARDS &
SPECIFICATIONS

REVISED:

TEMPORARY SEDIMENT
BASIN OUTLET

DATE:

DRAWING NO. 600-09

SEEDING AND MULCHING INSTALLATION NOTES

1. All brands furnished shall be free from such noxious seeds as Russian or Canadian thistle, course fescue, European bindweed, Johnson grass, Knap weed, and leafy spurge.
2. The seeder shall furnish to the Contractor a signed statement certifying that the seed furnished is from a lot that has been tested by a recognized laboratory. Seed that has become wet, moldy, or otherwise damaged in transit or in storage, will not be acceptable. Seed tickets shall be provided to the Engineer upon request.
3. Drill seeding mix shall conform to the seed mix table.
4. If the seed available on the market does not meet the minimum purity and germination percentages specified, the subcontractor must compensate for a lesser percentage of purity or germination by furnishing sufficient additional seed to equal the specified product. The tags from the seed mixes must be supplied to contractor and forwarded to the Engineer.
5. The formula used for determining the quantity of pure live seed (PLS) shall be (pounds of seed) X (purity) X (germination) = pounds of pure live seed (PLS).
6. Perminate seed mix shall be used unless otherwise approved by the Engineer.
7. All areas to be seeded and mulched shall have native topsoil or approved soil amendments spread to a depth of at least 6 inches (loose depth). Haul roads and other compacted areas shall be loosened to a depth of 6 inches prior to spreading topsoil.
8. Soil is to be thoroughly loosened (tilled) to a depth of at least 6 inches prior to seeding. The top 6 inches of the seed bed shall be free of rocks greater than 4 inches and soil clods greater than 2 inches. Seeding over any compacted areas that haven't been thoroughly loosened shall be rejected.
9. Seed is to be applied using a mechanical drill to a depth of 1/4 inch. Row spacing shall be no more than 6 inches. Material used for mulch shall consist of long-stemmed straw. At least 50 percent of the mulch, by weight, shall be 10 inches or more in length. Mulch shall be applied and mechanically anchored to a depth of at least 2 inches. Mulch shall be applied at a rate of 4000 Lb. of straw per acre.
10. If the permittee demonstrates to the Engineer that it is not possible to drill seed, seed is to be uniformly broadcast at two times the drilled rate, then lightly harrowed to provide a seed depth of approximately 1/4 inch, then rolled to compact, then mulched as specified above.
11. Seeding and mulching shall be completed within 30 days of initial exposure or 7 days after grading is substantially complete in a given area (as defined by the Engineer). This may require multiple mobilizations for seeding and mulching.
12. Mulch shall be applied within 24-hours of seeding.
13. Tackifier should be utilized to help with straw displacement.



STANDARDS &
SPECIFICATIONS

REVISED:

**EROSION AND SEDIMENT
SEED AND MULCHING**

DATE:

DRAWING NO. 600-10

DRILL SEEDING MIX

1. Seed shall be drilled only (no hydroseed).
2. Seed type and amount of pure live seed (PLS) required per acre shall be:

NATIVE AREA SEED MIX

SEED NAME	BOTANIC NAME	% IN MIX	POUNDS OF PLS PER ACRE
Slender Wheatgrass	Agropyron Trachycaulum	0%	3 lbs.
Mountain Brome	Bromus Marginatus	0%	3 lbs.
Indian Ricegrass	Oryzopsis Hymenoides	0%	2 lbs.
Thickspike Wheatgrass	Agropyron Dasystachyum	0%	2 lbs.
Western Wheatgrass	Agropyron Smithii	0%	2 lbs.
Arizona Fescue	Festuca Arizonica	0%	2 lbs.
Sandburg Bluegrass	Poa Sandbergii	0%	0.5 lbs.
Rocky Mountain Penstemon	Penstemon Strictus	0%	0.5 lbs.
Blue Flax	Linium Lewsii	0%	0.5 lbs.
Mountain Lupine	Lupinus Alpestris	0%	1 lbs.
Lance-leaved Coreopsis	Coreopsis Lanceolata	0%	0.5 lbs.
Rubber Rabbitbrush	Chysothanus Nauseosus	0%	0.5 lbs.
Fringed Sagebrush	Artemisia Frigida	0%	0.3 lbs.
Prairie Sage	Artemesia Ludoviciana	0%	0.2 lbs.
		TOTAL	22.5 lbs.

SWALES/DRAINAGE AREA SEED MIX

SEED NAME	BOTANIC NAME	% IN MIX	POUNDS OF PLS PER ACRE
Streambank Wheatgrass	Agropyron Riparium	0%	4 lbs.
Thickspike Wheatgrass	Agropyron Dasystachyum	0%	7 lbs.
Mountain Brome	Bromus Marginatus	0%	3 lbs.
Western Wheatgrass	Agropyron Smithii	0%	3 lbs.
Tufted Hairgrass	Deschampsia Caespitosa	0%	2 lbs.
Nuttall Alkaligrass	Puccinellia Airoides	0%	0.5 lbs.
Western Yarrow	Achillea Lanulosa	0%	0.5 lbs.
New England Aster	Aster Novae-angliae	0%	0.5 lbs.
Rocky Mountain Iris	Iris Missouriensis	0%	0.5 lbs.
		TOTAL	21.0 lbs.




STANDARDS &
SPECIFICATIONS

REVISED:

SEED MIX


DATE:

DRAWING NO. 600-11




SF

SILT FENCE EROSION BARRIER



SILT FENCE INSTALLATION

-NTS-



NOTE: EROSION CONTROL MEASURES SHALL BE MAINTAINED UNTIL LANDSCAPING IS COMPLETED.

SECTION

-NTS-




STANDARDS &
SPECIFICATIONS

REVISED:


SILT FENCE
EROSION BARRIER

DATE:


DRAWING NO. 600-12



VEHICLE TRACKING CONTROL



NOTE: EROSION CONTROL MEASURES SHALL BE MAINTAINED AT ALL TIMES AS DIRECTED BY THE CITY ENGINEER



SECTION A-A
-NTS-

NOTES

1. ALL ROCK TO BE REMOVED UPON COMPLETION OF CONSTRUCTION.
2. PUBLIC ROADWAY TO BE KEPT CLEAN AND FREE OF MUD, DIRT AND DEBRIS AT ALL TIMES.




STANDARDS &
SPECIFICATIONS

REVISED:

VEHICLE TRACKING
CONTROL


DATE:

DRAWING NO. 600-13




STB

STRAW BALE EROSION BARRIER




TRENCH EXCAVATION

-NTS-



STRAW BALE INSTALLATION

-NTS-



NOTE: EROSION CONTROL MEASURES SHALL BE MAINTAINED UNTIL LANDSCAPING IS COMPLETED.

SECTION

-NTS-




STANDARDS &
SPECIFICATIONS

REVISED:


STRAW BALE
EROSION BARRIER

DATE:

DRAWING NO. 600-14



PLAN



PROFILE

OUTLET STRUCTURE



STANDARDS &
SPECIFICATIONS

REVISED:

**OUTLET
STRUCTURE**

DATE:

DRAWING NO. 600-15